

# yquant.sty package documentation

Typesetting quantum circuits in a human-readable language

Benjamin Deseff

August 17, 2021

This manual introduces `yquant`, a  $\text{\LaTeX}$ -only package that outputs quantum circuits. They are entered using a human-readable language that, even from the source code, allows for a fluent understanding of the logic that underlies the circuit. `yquant` internally builds on `TikZ` and can be easily combined with arbitrary  $\text{\LaTeX}$  code. More than fifty pages of examples complement the formal manual.

## Contents

<b>1</b>	<b>Introduction</b>	<b>4</b>
1.1	How to read the manual . . . . .	4
1.2	Installation . . . . .	4
1.3	Purpose of <code>yquant</code> , alternatives . . . . .	5
1.4	License . . . . .	6
<b>2</b>	<b>Basic elements of <code>yquant</code></b>	<b>7</b>
2.1	General usage . . . . .	7
2.2	Starred vs. unstarred environment . . . . .	8
2.3	Formal syntax . . . . .	9
2.4	Registers . . . . .	10
2.5	Arguments . . . . .	13
2.6	Controls . . . . .	14
2.7	Importing circuit from files . . . . .	14
2.8	Defining own gates . . . . .	15
<b>3</b>	<b>Configuration</b>	<b>18</b>
3.1	Circuit layout . . . . .	18
3.2	Register creation . . . . .	19
3.3	Register outputs . . . . .	21
3.4	General styling . . . . .	22
3.5	Styles for operators . . . . .	25
<b>4</b>	<b>Doing the impossible</b>	<b>30</b>
4.1	Mixing <code>yquant</code> and <code>TikZ</code> code . . . . .	30
4.2	Accessing gates in <code>TikZ</code> . . . . .	30
4.3	Shapes and the drawing pipeline . . . . .	31
4.4	Overwriting the height and depth calculation . . . . .	32
<b>5</b>	<b>Reference: Gates and operations</b>	<b>35</b>
5.1	<code>addstyle</code> . . . . .	35
5.2	<code>align</code> . . . . .	35
5.3	<code>barrier</code> . . . . .	35
5.4	<code>box</code> . . . . .	36
5.5	<code>cbit</code> . . . . .	36
5.6	<code>correlate</code> . . . . .	36
5.7	<code>cnot</code> . . . . .	36
5.8	<code>discard</code> . . . . .	36

5.9	<code>dmeter</code>	37
5.10	<code>h</code>	37
5.11	<code>hspace</code>	37
5.12	<code>init</code>	37
5.13	<code>inspect</code>	38
5.14	<code>measure</code>	38
5.15	<code>nobit</code>	39
5.16	<code>not</code>	39
5.17	<code>output</code>	40
5.18	<code>phase</code>	40
5.19	<code>qubit</code>	40
5.20	<code>qubits</code>	41
5.21	<code>setstyle</code>	41
5.22	<code>settype</code>	42
5.23	<code>setwire</code>	42
5.24	<code>slash</code>	42
5.25	<code>subcircuit</code>	42
5.26	<code>swap</code>	44
5.27	<code>x</code>	44
5.28	<code>xx</code>	44
5.29	<code>y</code>	44
5.30	<code>z</code>	45
5.31	<code>zz</code>	45
<b>6</b>	<b>Examples</b>	<b>46</b>
6.1	<code>qasm</code> documentation	46
6.2	<code>qcircuit</code> documentation	57
6.3	<code>quantikz</code> documentation	72
<b>7</b>	<b>Foreign language support and extensions</b>	<b>96</b>
7.1	groups	96
7.2	qasm	101
<b>8</b>	<b>Wishlist</b>	<b>107</b>
<b>9</b>	<b>Changelog</b>	<b>108</b>

# 1 Introduction

This document outlines the scope and usage of the `yquant` package. It contains both a reference and a huge number of examples. `yquant` is a package that makes typesetting quantum circuits easy; the package is available on CTAN. This beta version 0.5 *should* be stable and interfaces are not very likely to change in an incompatible way in the future. Sometimes, backwards-incompatible changes are required or advisable, in which case a compatibility setting will allow to revert back to the old behavior (rather, to maximize compatibility, this is an opt-in setting: unless you choose the new behavior, you will get the old one). Please do report all issues and desirable additions on [GitHub](#).

New in 0.4

## 1.1 How to read the manual

The probably fastest way to start using `yquant` is by just scanning through the examples in section 6. A more formal description of the `yquant` grammar and its fundamental concepts can be found in section 2. If your desire is to change the appearance of `yquant` elements, use the configuration reference in section 3. The full list of all available gates is provided in section 5. Finally, you may find that `yquant` *almost* does what you want, but there is some final tweak that you cannot achieve.... Then, have a look at section 4 (or section 1.3).

## 1.2 Installation

The recommended way of installation is through CTAN. A direct installation from the Git repository to obtain the latest additions and features is possible by just cloning it to a path visible to your  $\text{\TeX}$  compiler. For example, you may put the source files in the same directory as your document (if you just want to give a try), or you may extract them to `tex/latex/yquant` in your local `texmf` (followed by an update of the file name database). While the repository may contain new additions, they are not thoroughly tested until they end up on CTAN; features that are not documented in this manual are entirely unreliable.

The CTAN repository reflects the most current version tag on Git; the [Releases](#) section on GitHub additionally provides a single-file version of the main package, which can for example conveniently be included in arXiv submissions. Note that the arXiv currently provides `yquant` 0.3.2 out-of-the-box.

New in 0.4

### 1.3 Purpose of `yquant`, alternatives

`yquant` is the acronym for “yet another quantum circuit package.” This highlights the fact that nothing that this package provides cannot be achieved by other means. In particular, there are at least the following methods to typeset quantum circuits in  $\text{\TeX}$ .

- Use some external program to draw them and include the output via `\includegraphics`.
- Use either  $\text{\TeX}$ ’s own drawing capabilities (the `picture` environment) or other drawing packages such as `TikZ` or `pstricks`.
- Use a package specifically designed to draw quantum circuits (if you feel some other package should be mentioned here, please file an issue):
  - `qasm` is probably the first of them (in terms of age). It was developed to typeset the circuits found in Nielsen and Chuang’s famous *Quantum Computation and Quantum Information* book. `qasm` consists of a Python 2 script (`qasm2circ`) that reads a quantum circuit written in a very intuitive language: declare names for your qubits, perform gates on them in each line. `qasm2circ` converts those circuits into  $\text{\TeX}$  files that internally make use of the `xy` package to display the output. Consequently, the user is restricted to the set of features that `qasm` directly offers (which is small). Changes to the output, while possible, will be overwritten if `qasm2circ` is run again. `qasm` output often looks sub-optimal due to the fact that, e.g., rectangles are made up of four lines that do not properly connect and give a crumbly general feeling. Note that since version 0.3, `yquant` understands `qasm` syntax, see section 7.2.  
  
Maintenance status: last update of `qasm` in 2005. Also, `xy` was last updated in 2013, and the script is not compatible out-of-the-box with Python 3, though an automatic conversion should work.
  - `qcircuit` is probably the most-widely used package. It provides commands that make it much easier to create quantum circuits using the `xy` package. Its syntax therefore is grid-oriented; inferring what a circuit does or locating a gate in the code can be tough. This is particularly true for multi-qubit gates. Additionally, the `\xymatrix` syntax is also somewhat cryptic. `qcircuit` provides some flexibility within the limits of `xy` as to configuring the output.

Maintenance status: last update in 2018; and remember this is `xy` based, with last update in 2013.

- `quantikz` is a relatively recent package that, following the same grid-based approach as `qcircuit`, instead builds on `TikZ` as a backend. As a consequence, it provides the full flexibility of customization that `TikZ` offers, where hardly anything cannot be done. It also reduces burdens of the `xy` syntax. However, the disadvantages of the grid-based syntax still remain.

Maintenance status: last update in 2020; the underlying `TikZ` is actively maintained again by now.

- `qpic` follows the approach of `qasm`: It makes use of an external Python program that reads the quantum circuits in an own language and converts them into `TikZ` commands. The language `qpic` follows is much more powerful than `qasm`'s. The disadvantage that modifications in the output code will not remain after running the Python script again is mitigated by the possibility to define own  $\TeX$  macros. Being an external program, `qpic`'s intrinsic set of features (including, e.g., vertically set circuits) are huge. However, the language `qpic` uses cannot be understood without a detailed study of the manual, it appears to have been designed with the aim to minimize the length of command names. A disadvantage of external programs is that the amount of space gates need is not accessible by the script; hence, manual intervention may be required.

Maintenance status: last update in 2020; the underlying `TikZ` is actively maintained, and the script is compatible with Python 3.

## 1.4 License

This work may be distributed and/or modified under the conditions of the  $\TeX$  Project Public License, either version 1.3c of this license or (at your option) any later version. The latest version of this license is in

<http://www.latex-project.org/lppl.txt>

and version 1.3c or later is part of all distributions of LaTeX version 2005/12/01 or later.

## 2 Basic elements of `yquant`

`yquant`, as some of the aforementioned packages, builds on `TikZ`. Its basic syntax is similar to `pgfplots`: Start a `tikzpicture` environment (perhaps passing some options); inside, start a `yquant` environment.

Inside the `yquant` environment,  $\text{\TeX}$  will now understand the `yquant` language—so `yquant` falls into the same category as `qasm` and `qpqc`, providing a human-readable language for the specification of the circuit that is not fixed to the actual layout.

However, `yquant` is a  $\text{\TeX}$ -only package (actually,  $\text{\TeX}2_{\epsilon}$ , but not  $\text{\TeX}3$ ) that requires no external script to run—so it also falls into the same category as `qcircuit` and `quantikz`.

Since it runs entirely within  $\text{\TeX}$ , you can at any time interject `yquant` code with arbitrary  $\text{\TeX}$  or `TikZ` code (though if it is “too arbitrary,” you may need to restart the `yquant` interpreter).

### 2.1 General usage

```
% preamble: \usepackage[compat=<version>]{yquant}
\begin{tikzpicture}% tikz options possible
  % tikz commands go here
  \begin{yquant}% yquant options possible. Watch the newlines!
    % yquant and tikz commands go here
  \end{yquant}
  % tikz commands go here
\end{tikzpicture}
```

Changed in 0.4

Note that `yquant` depends on `etoolbox`, `TikZ`, `trimspaces`, and `xkeyval`. Additionally, it requires a moderately recent version of  $\text{\TeX}2_{\epsilon}$ , using either  $\text{\LaTeX}$ ; or (untested)  $\text{\pdf\TeX}$  or  $\text{\Xe\TeX}$ .

Changed in 0.4



#### Optional arguments

The optional arguments for the `yquant` environment have to appear *on the same line* as the environment itself. If you want to put the arguments into a new line, it is crucial to mask the line break by putting a comment symbol after the environment: `\begin{yquant}%`. Without this comment, `yquant` will detect your line break (this is one of the few places in  $\text{\TeX}$  where line breaks and spaces are different) and assume that the expression in square brackets instead provides arguments for the following operation!

Finally note that in (non-fragile) `beamer` frames, this discrimination between

spaces and new lines does not work; the optional arguments will always be counted for the environment, not for the gate. In this case, you can either declare the frame as fragile or (recommended) introduce a blank line between the environment and the options for the first gate.



### Compatibility mode

New in 0.4

Sometimes, continued development shows that certain choices of interfaces, configuration, or behavior are less ideal than originally thought. In other cases, bugs are detected and fixed. Both may lead to a change in the look of circuits developed with a previous version of `yquant` or even—though this should rarely, if ever, happen, and should be filed as a bug—prevent compilation in the new version.

For this reason, `yquant` offers a compatibility key that is highly recommended to be specified as a package option. This allows certain features that are expected to break old layout or functionality to revert to their previous behavior. Every feature affected by the `compat` key is documented in this manual. Once a compatibility version is selected in a document, it cannot be changed any more. Compatibility versions will include the major and minor, but not the patch level version number (though not every major or minor version will necessarily introduce new compatibility versions). Bugs that clearly violated behavior described in this manual will be fixed without a possibility to revert back. Changes that are not supposed to result in a (more than marginally) different result will not be included in the compatibility layer. If you find this to be wrong in a particular case, please file a bug report.

When starting a new document, it is recommended to leave out the compatibility key at first compilation. `yquant` will then issue a warning from which you can infer the recommended setting, corresponding to the current version. You should then pass the appropriate version to the `\usepackage` command. For example, this manual corresponds to `\usepackage[compat=0.4]{yquant}`. Allowed values for `compat` are `newest` (discouraged), which equals 0.4, and 0.3 (default).

## 2.2 Starred vs. unstarred environment

You may choose to use either the `yquant` or the `yquant*` environment. The former one requires you to define all your registers before you use them (though you may decide to define a register after some operations on *different* registers, but before its first usage).



The starred form additionally supports the use of undeclared registers: it basically declares a registers upon its first usage. This will always be a qubit register; but if you use the corresponding attribute and the first usage is an `init` command, you may overwrite this.

Subcircuits always use the unstarred form.

New in 0.2  
New in 0.1.1

Additionally, if you refer to the index  $i$  of a vector register of length  $L < i$ , this register will automatically be enlarged to  $i := L$ . It is also possible to convert a scalar register into a vector register in this manner. To enlarge a register in the unstarred environment, you must precede the number of registers to be added in the second declaration by a plus sign. Note that in this manner, you may even create discontinuous vectors.

*This might be a good point to proceed to the examples section 6.*

## 2.3 Formal syntax

Enhanced in 0.1.2,  
0.1.1

Every `yquant` command has the same structure (described here in EBNF syntax):

```
Command = { Arguments }, ?command?, [ Value ], [ RegisterList ], Controls,
↪ ";";
Arguments = "[", ?pgfkeys?, "[";
Value = "{", ?TeX code?, "}";
Controls = [ "|", [ RegisterSingleList ] ], [ "~", [ RegisterSingleList ] ];

RegisterList = (RegisterSingle | RegisterMulti), [ ",", RegisterList ];
RegisterSingleList = RegisterSingle, [ ",", RegisterSingleList ];

RegisterSingle = RegisterSingleNoRange | RegisterRange;
RegisterSingleNoRange = ?name?, [ "[", IndexMultiList, "]" ];
RegisterMulti = "( ( RegisterMultiNoRange | [ "*" ], RegisterRange ), )";
RegisterMultiNoRange = [ "*" ], ?name?, [ "[", IndexSingleMainList, "]" ];
RegisterRange = [ RegisterUnique ], "-", [ RegisterUnique ];
RegisterUnique = ?name?, [ "[", ?number?, "]" ];

IndexMultiList = IndexMulti, [ ",", IndexMultiList ];
IndexSingleList = IndexSingle, [ ",", IndexSingleList ];
IndexSingleMainList = [ "*" ], IndexSingle, [ ",", IndexSingleMainList ];
IndexMulti = IndexSingle | ( "(", IndexSingle, ")" );
IndexSingle = ?number? | ( [ ?number? ], "-", [ ?number? ] );
```

Note that `yquant` is quite tolerant with respect to whitespaces. Virtually every comma in the EBNF notation may consist of an arbitrary (including zero) number of whitespaces. Not all combinations that can be constructed by this grammar are actually allowed semantically; but it would make the grammar too verbose to spell this out in detail. Deviations are noted in this manual.

Valid values for `?command?` (case-insensitive) are documented in a section 5. We use `?pgfkeys?` to describe any valid content passed to the `\pgfkeys` macro (rather, `\yquantset` is invoked with some subtleties); and by `?name?` we denote any valid register name. Register names must not contain any of the control literals used before (semicolon, comma, parentheses, square brackets, dash, pipe, tilde, beginning star); and you should avoid using special T<sub>E</sub>X characters. Note that for performance reasons, `yquant` does not check whether a register name is valid or not, but expect to either see unintended output or not-so-helpful error messages if you choose an invalid name. `?number?` is a decimal integer larger or equal to zero (in the context of register creation, strictly larger; in this context, it may also contain a leading "+").

## 2.4 Registers

Every quantum circuit is structured by means of *registers*. A register has a *type* that specifies how its wire is drawn, and that may even change during its lifetime. At the moment, `yquant` supports four types:

1. `qubit` is the most common type, used for a quantum register. It corresponds to a single line.
2. `cbit` is a classical register, which can be either declared from the beginning or arises by using measurements. It corresponds to a double line.
3. `qubits` is a “quantum bundle,” i.e., a bunch of quantum registers that are always addressed in a group as a single register. Operations between bundles of the same length should be interpreted as transversal. It corresponds to a triple line. An alternative (and more common) representation is to use the `qubit` type and a `slash` gate at its very beginning.
4. `nobit` is the most obscure type, corresponding to a non-existing wire. Mostly, this register type arises by using the `discard` command. However, it can also be directly declared, which on rare occasions might be necessary (its type can then be changed by means of an `init` or `setwire` pseudo-gate). If you want to declare a register only at a certain horizontal position in the circuit, consider using the `after` argument instead.

Registers must be declared before they can be used (though in the `yquant*` environment, this declaration may be implicit, creating a `qubit` register).

Registers can have a vector character, i.e., not only a *name*, but also an *index* (or, in the declaration, a *length*). The index (zero-based) or length is specified

in square brackets following the name, which closely mimics the OpenQASM language.

Vector registers may be non-contiguous: Whenever you create a bunch of registers, it is put at the bottom of the circuit. If you later on again create registers of the same name—either implicitly in the `yquant*` environment, or explicitly by preceding the length of the vectors entries to be added by a plus, as in `qubit a[+3]`;—they will be put to what is *now* the bottom of the circuit, even if some other registers are interspersed.

New in 0.1.1

Registers are referenced—i.e., used in operations—by their name and index. If the latter is omitted, all indices of the register are targeted. Multiple registers can be referenced by joining their names in a comma-separated list, or by means of a range specifier: give the name of the first (topmost), a dash, and the last (bottom-most) register. Both are inclusive. In a range specifier, omitting the start name means that the range begins at the first known register; omitting the end name means that the range ends at the last known (at the moment of its use) register. Omitting both indicates a range over all known registers.

It is also possible to use comma-separated lists and ranges within the indices themselves, so that, e.g., `a[0, 2, 5-]`, `b[-2]` will target the zeroth and second index of `a`; the remaining indices of `a` starting from five; and the first three indices of `b`. However, if you use an *outer* range (i.e., a range between indices of registers with different names), the initial and final register of the range must be unique, i.e., either you omit the index (targeting the first or last register with the given name) or specify a single one.

New in 0.1.1



#### Ranges and discontinuous registers

Assume a configuration in which the vector register `a` begins with one qubit, then the single register `b` follows, and after that `a` is continued with another qubit.

The range `a-b` will target `a[0]` and `b[0]`, but not `a[1]`. As `a` is used as the initial register in the range without an explicit index specification, `yquant` automatically translates this into `a[0]`, while `b`, being used as the final register, is automatically translated into the last register of name `b` (which here happens to be `b[0]`). Ranges between different register names (outer ranges) are *visual* ranges, i.e., they refer to the top-to-bottom order that is visible. Consequently, the register `a[1]` is left out since it is visually below the others.

Likewise, the range `b-a` will target `b[0]` and `a[1]`.

Ranges within indices are *logical* ranges. Hence, `a`, `a[-]`, `a[0-]`, `a[-1]`, and `a[0-1]` are all equivalent: they all refer to the registers `a[0]` and `a[1]`, but never to `b`, regardless of any visual position.

All that was said so far refers to the operation being carried out on each of the registers *individually*, i.e., producing several copies of the operation. This is different from using the operation multiple times on the individual single registers only with regard to the horizontal positioning: if specified as a register list with one operation, all copies of the operation will be aligned at the same horizontal middle axis (for gates with the same width on each register, this is the same as issuing an `align` command before performing the operations individually).



It is forbidden (in the sense of “not useful and giving unexpected output,” but `yquant` does not check for this) to list the same register multiple times (explicitly or via ranges) in one operation.

Instead of copies of single-register operations, one might want to carry out a multi-register operation. In this case, the desired list of registers (comma separated, range, or both) must be surrounded by parentheses. It is possible to mix single- and multi-register operations arbitrarily. In an index list, you may also choose to surround only certain indices with parenthesis, provided the whole register is not already a multi-register.



Note that some gates, such as the `swap` gate, always require (semantically, not grammatically) multi-register operations. The number of constituents is not stipulated; while a `swap` gate with more than two targets is no longer well-defined, other registers such as `zz` may still be useful. `yquant` will prevent you from using a gate in a multi-qubit setting when it may only be used for single registers.

Changed in 0.1.2

Typically, multi-register operations should only be carried out on adjacent registers—but sometimes, one might want to carry out a multi-qubit operation on a visually discontinuous set of registers (which, due to a particular quantum computer topology, might even be physically feasible). `yquant` supports these discontinuous operations explicitly. It will draw a *main* part of the gate at the first contiguous slice of registers in the target list—you may select another register for this part by preceding the name or index with a star (which, contrary to the simplified grammar, may only occur *once* in a target specification). All other contiguous slices of target registers will be drawn in a *subordinate style* for this gate. Finally, all slices will be connected by a single vertical line with the style `/yquant/every multi line`. Subcircuits will always span the full region from the first to the last register specified in a multi-qubit gate. This is due to the fact that they may contain arbitrary ancilla registers which may be positioned somewhere in between the parts that actually constitute the subcircuit—surrounding this with a scattered set of connected boxes would look quite unpleasant.

New in 0.1.2

New in 0.2



### Discontiguous targets and control lines

A control line extends from the very first to the very last affected register in an operation. A sub-gate line that is used for discontiguous registers will only span the range of a multi-register. This distinction becomes crucial if you want to carry out a *controlled* operation on more than one multi-register, where at least one is discontiguous. Without the controls, the separate multi-registers could be identified, since no connecting vertical line extends between them (unless, which you should strictly avoid, they are intertwined). However, with the controls, the control line will make it hard (for some gates, impossible) to visually distinguish the connected parts. `yquant` will kindly provide a warning in this case. You may choose to suppress this warning using the boolean key `/yquant/operator/multi warning`.



There is no established style for discontiguous gates. Note that at the moment, main and subordinate style coincide for all gates except for the `measure` gate with a value. In order to still make it possible to visually distinguish discontiguous multi-register gates operating on slices of a single register from just a bunch of single-register gates that are executed in a parallel manner if controls are present, `yquant`'s default vertical line style for the former case is a wavy line instead of a straight one. Still, the meaning of this should probably be explained. Please feel free to submit issues or pull requests with propositions of how default styles or alternative subordinate gate shapes may additionally help to mitigate the problem.

## 2.5 Arguments

Every command may take one or multiple arguments. Those are specified in square brackets that precede the command itself. The content of those square brackets is essentially fed to a `\pgfkeys`-like macro. The default path is set appropriately such that the arguments of the command can be accessed without path specifiers. If the key is not a valid argument for the command or a global argument and it is not given by an absolute path, it is searched for in the `/yquant` namespace. If it cannot be found there, it is passed to `/yquant/operator style`.

Note that commands may have required arguments. If a required argument is missing, an error will be issued.

The `value` attribute can alternatively be given inside curly brackets after the command name and before the register specification. This has the advantage that special characters such as a closing square bracket need not be escaped. If both

alternatives are present, the value inside curly brackets takes precedence and a warning is issued.

## 2.6 Controls

Lots of gates may have controls, i.e., they are only to be executed if some other gate is set or unset. The former case is called a *positive control*, the latter one a *negative control*. Those are indicated by filled and empty circles on the control registers and a vertical line that joins the registers that belong together.

The gate specification is followed by the list of target registers. By then writing a pipe (“|”), the list of positive controls is introduced; this mimics the mathematical syntax “conditioned on” for probabilities or “given” for sets. If there are no positive controls, the list may be empty or, together with the pipe, omitted. Preceded by a tilde (“~”), the list of negative controls then follows; this mimics the syntax of many programming languages that denote logical negation by a tilde. If there are no negative controls, the list may be empty or, together with the tilde, omitted.

## 2.7 Importing circuits from files

New in 0.2

`yquant` provides a simple way to import circuits that are stored in external files. The macro `\yquantimport` can be used in three different contexts:

- Outside of a `TikZ` picture environment.

Here, `\yquantimport[<options>]{<filename>}` will be equivalent to

```
\begin{tikzpicture}
  \begin{yquant}[<options>]
    % the content of <filename> goes here
  \end{yquant}
\end{tikzpicture}
```

The starred form, `\yquantimport*[<options>]{<filename>}`, instead inserts the starred `yquant` environment. Note that the options are always `yquant` options; if you want to pass `TikZ` options, you will have to create the picture environment by yourself or change the option path to the correct one (`/tikz/.cd`).

- Inside a `TikZ` picture environment, but outside of a `yquant` environment. This is the same as before, just that no extra picture environment will be added.

- Inside both a `TikZ` picture environment and a `yquant` environment. The file will be inserted directly into the environment. `yquant`'s parser is automatically restarted after this. The content will always be put in a  $\TeX$  group; if additional options are provided, `yquant` also inserts a `TikZ` scope and executes `\yquantset{<options>}` directly after the scope. If `\yquantimport` is used, the content will be read as if the containing environment was an unstarred one; if `\yquantimport*` is used, the content will be read as if the containing environment was a starred one.

Note that `yquant` internally uses plain  $\TeX$ 's `\import` command (i.e., `\@@import` in  $\LaTeX$ ). However, when the `import` package is loaded, it uses `\subimport{\yquantimportpath}{<filename>}`, where `\yquantimportpath` defaults to `./`—so by changing this, files from other folders may be imported which by themselves again include other files, and the relative path resolution will work.

Note that you may in particular import the content of a `subcircuit`.

## 2.8 Defining own gates



### Scope

All gate declarations are always global.

If you want to define a gate that corresponds to a single `box` gate with a certain pre-defined content, you may use the macro

`\yquantdefinebox{<name>}[<style>]{<content>}`, which is far more efficient than the much more general `\yquantdefinegate` introduced below. It only allows for single-register usage; use `\yquantdefinemultibox` with the same arguments if you want to allow the gate to be used in a multi-register gate fashion. The macros work in the following way:

New in 0.2.1

New in 0.4

- They create a new gate with name `<name>` that can be accessed as all the other build-in gates. Note that `<name>` is case-insensitive and may not contain spaces. Special characters are allowed if  $\TeX$  can cope with them (i.e., no comment signs, no unbalanced braces, no backslashes...).
- They create a style `/yquant/operators/every <name>` and assign the optional `<style>` to it. If no style is provided, the default style will inherit from `/yquant/operators/every box`.
- They define `<content>` to be the value that is written into the box. This `<content>` is expanded in a protected manner at the time of gate declaration. You may need to prefix fragile macros by `\protect`.

Sometimes, you may wish to define gates that are more than just a single box—perhaps a succession of multiple gates or even multi-register gates with individual operations on the input registers. `yquant` provides a simple macro that allows this. The macro `\yquantdefinegate{<name>}[<style>]{<content>}` works in the following way:

- It creates a new gate with name `<name>` that can be accessed as all the other built-in gates. Note that `<name>` is case-insensitive and may not contain spaces. Special characters are allowed if  $\text{\TeX}$  can cope with them (i.e., no comment signs, no unbalanced braces, no backslashes...).
- It creates a style `/yquant/operators/every <name>` and assigns the optional `<style>` to it. If no style is provided, the default style will inherit from `/yquant/operators/every custom gate`. This will make the gate “seamless,” i.e., avoid highlighting the fact that this is a custom gate.
- It defines a macro that contains `<content>` (expanded in a protected manner) and that will be inserted as a subcircuit whenever this gate is invoked. This in particular means that if you use `\yquantimport` within the gate, the file will only be loaded once at the time of declaration.

When the gate is later drawn, the styles are invoked in the following order—remember custom gates are implemented by means of subcircuits—:

1. `/yquant/every operator`
2. `/yquant/operators/every <name>`
3. `/yquant/operators/every subcircuit box`
4. `/yquant/this operator`
5. `/yquant/operators/this subcircuit box`

Gates defined in this way can only make use of the default gates or other custom gates. They do not accept custom arguments, and it is not possible to declare own, custom shapes in this way (though other predefined shapes may be used). If they are used in a multi-qubit manner, they will never be split into contiguous slices (but their content will be, so if you use the default style that turns off the box, the only way to notice this is that intermediate unaffected registers will not be allowed to have gates visually within the rectangle that would bound the custom gate).





### Redefining existing gates

The above macros will issue an error if the gate already exists. You can use `\yquantredefinebox`, `\yquantredefinemultibox` (use the appropriate command for the *new* definition), or `\yquantredefinegate` to overwrite existing gate definitions. Note that this will overwrite *any* gate, even the built-in ones. Generally, it is discouraged to make use of this possibility. For custom gates, if you redefine a gate as a box which was previously a general subcircuit-based gate, the macro that contains the subcircuit will still be held in memory. Overwriting built-in gates will not clear the attributes associated to this gate (though required attributes will no longer be required afterwards). Again, this is not a problem but prevents `yquant` from issuing potentially helpful error message if such a—now meaningless—attribute is used. Finally, once a built-in gate is overwritten, it cannot be restored. In particular, the register creation pseudo-gates `qubit`, `cbit`, `qubits`, and `nobit` perform some magic that cannot be mimicked with custom gates.

More advanced declaration of custom gates requires the use of backend macros. Refer to `yquant-lang.tex` for this. Note that the backend interface changed in version 0.4. For the declaration of custom shapes, see `yquant-shapes.tex` for examples.

## 3 Configuration

`yquant` uses `pgfkeys` to control its options, which are located in the path `/yquant`. The following list contains all options and styles that are recognized, apart from gate arguments. Those are listed together with their operations.

### 3.1 Circuit layout

`/yquant/register/minimum height` default: 1.5mm    Changed in 0.4

`yquant` automatically determines the height (extent from wire to top boundary) of a register as the height of the largest operation. This might be too small for two reasons:

- if the register is used only with small gates (e.g., only as a control, or as a swap), and it does not have a label (or one containing only x-height letters).
- if you manually turned off height calculation or multi-extent calculation for a large gate. `yquant` will then not consider the vertical extent of this gate, which might consequently lead to undesirable overlaps.

This key provides an easy alleviation of the problem by requiring a minimal height for every register. As the value of this key is relevant at the time of register declaration, it can also be changed for each register individually.

Note that this key is affected by the `compat` setting. Before version 0.4, there was no `/yquant/register/minimum depth` key. In this compatibility setting, passing the value  $x$  to this key will set both height and depth to  $\frac{x}{2}$ . The default for  $x$  is then 3mm.

`/yquant/register/minimum depth` default: 1.5mm    New in 0.4

see `/yquant/register/minimum height`

This key allows to specify a minimum depth (extent from wire to bottom boundary) for a register.

Note that this key is affected by the `compat` setting. Before version 0.4, this key will not be available.

`/yquant/register/separation` default: 1mm

This key controls the amount of vertical space that is inserted between two successive registers. Half of this value is also the length that multi-`init` or multi-`output` braces extend beyond the mid position of the register.

`/yquant/operator/minimum width` default: 3mm

`yquant` automatically determines the width of an operator according to its content. However, single-letter boxes are among the most common operators, and giving them slightly different widths would result in a very uneven spacing, as `yquant` does not use a grid layout but stacks the operators horizontally one after each other. Hence, this key provides a minimum width that will be set for every operator. This does not imply that the *visual* appearance (i.e., the `x radius` key) is enlarged, but that operators of a smaller actual width will be centered in a virtual box of the minimum width.

`/yquant/operator/separation` default: 1mm

This key controls the amount of horizontal space that is inserted between two successive operators and at the beginning and end of a circuit.

`/yquant/operator/multi warning` default: true New in 0.1.2

If this key is `true`, a warning is displayed whenever more than a single multi-register gate, where at least one is discontinuous, is employed together with controls. Even if a visual distinction between control and multi-qubit line may be possible (depending on the style in use), they will overlap and produce unaesthetic output. You may disable this warning globally, on a per-circuit, or even on a per-gate basis.

### 3.2 Register creation

`/yquant/register/default name` default: `\regidx`

The printed name that is used by default if a new register is created explicitly (`qubit`, `cbit`, `qubits`; not used for `nobit` or for implicit declarations) and no value is specified. The following macros are available:

- `\reg` contains your name to identify this register.
- `\idx` contains the index (zero-based) of the current register within a vector register.
- `\regidx` expands to `\reg` if the register is of length one, and to `\reg[\idx]` else.
- `\len` contains the length of the current register vector.

`/yquant/every label` default: `shape=yquant-init, anchor=center, align=right, outer xsep=2pt, /yquant/operator/if multi={draw, decoration={gapped brace, mirror, raise=2pt}}, decorate}` Changed in 0.4

This style is installed for every single register name label (i.e., upon creation and when used with the `init` gate). The default style allows to use line breaks in the labels. The node shape, `yquant-init`, will generate a path at its right side, which is replaced by the gapped brace decoration if the gate is used in a multi-register fashion. The decoration is similar to `TikZ`'s brace decoration, but additionally allows specify the regions in which a line should be drawn by using the `/tikz/decoration/from to` key, which expects a comma-separated list of dimension ranges, and which is automatically populated by `yquant`. Note that if the `compat` key is below 0.3, the multi options are instead read from `/yquant/every multi label`.

`/yquant/every initial label` default: `anchor=east` Changed in 0.4

This style is installed for every single register name label at the left border of the circuit. It is therefore used if a label is specified upon declaration and also for the `init` gate if it happens to be the first gate on an unlabelled register (use a zero-width `hspace` gate before if you want to suppress this).

`/yquant/every qubit label` default:

This style is installed for every single register name label of a register of type `qubit`.

`/yquant/every cbit label` default:

This style is installed for every single register name label of a register of type `cbit`.

`/yquant/every qubits label` default:

This style is installed for every single register name label of a register of type `qubits`.

`/yquant/every multi label` default: `draw, decoration={gapped brace, mirror, raise=2pt}, decorate` Removed in 0.4  
Changed in 0.1.2

This style is installed for every register name label that is attached to a multi-qubit register by means of the `init` gate. Note that this key is only available if the `compat` setting is smaller than 0.4. In newer versions, this is incorporated in `/yquant/every label`.

<code>/yquant/every input label</code>	default:	Removed in 0.4 New in 0.2
--	----------	------------------------------

This style is installed for every register name label in a `subcircuit` when the register is an input (or input and output) register.

Note that this key is only available if the `compat` setting is smaller than 0.4; and in this case, it behaves inconsistently, as it is only applied for labels directly specified during creation, but not for initial `init` gates.

### 3.3 Register outputs

<code>/yquant/every output</code>	default: <code>shape=yquant-output, anchor=west, align=left, outer xsep=2pt, /yquant/operator/if multi={draw, decoration={gapped brace, raise=2pt}, decorate}</code>	Changed in 0.4
-----------------------------------	--	----------------

This style is installed for every `output` label at the end of the circuit. The default style allows to use line breaks in the labels.

The node shape, `yquant-output`, will generate a path at its left side, which is replaced by the `gapped brace` decoration in the case of multi-register usage. See `/yquant/every label` for a more detailed explanation.

<code>/yquant/every qubit output</code>	default:
This style is installed for every <code>output</code> label of a register of type <code>qubit</code> .	

<code>/yquant/every cbit output</code>	default:
This style is installed for every <code>output</code> label of a register of type <code>cbit</code> .	

<code>/yquant/every qubits output</code>	default:
This style is installed for every <code>output</code> label of a register of type <code>qubits</code> .	

<code>/yquant/every multi output</code>	default: <code>draw, decoration={gapped brace, raise=2pt}, decorate</code>	Removed in 0.4 Changed in 0.1.2
---	--	------------------------------------

This style is installed for every `output` label that is attached to a multi-qubit register.

Note that this key is only available if the `compat` setting is smaller than 0.4. In newer versions, this is incorporated into `/yquant/every output`.

### 3.4 General styling

`/yquant/every circuit` default: `every node/.prefix style={transform shape}` Changed in 0.4, 0.1.2

Style that is installed for every `yquant` and `yquant*` environment, as if it had been given as an option. The style's default path is, as with all other styles, `/tikz`. The style is re-applied for every subcircuit. The default style will make all nodes (which in particular means, all gates) respect outer canvas transformations.

If your `TikZ` version is before 3.1.6a, this style will additionally contain `every label/.prefix style={transform shape=false}`, which undoes the effect for labels (see `TikZ` bug #843). An update is recommended.

`/yquant/every wire` default: `draw`  
This style is installed whenever a wire is drawn.

`/yquant/every qubit wire` default:  
This style is installed whenever a wire for a register of type `qubit` is drawn.

`/yquant/every cbit wire` default:  
This style is installed whenever a wire for a register of type `cbit` is drawn.

`/yquant/every qubits wire` default:  
This style is installed whenever a wire for a register of type `qubits` is drawn.

`/yquant/every control line` default: `draw`  
This style is used to draw the vertical control line that connects controlled operations and their controls.

`/yquant/every control` default: `shape=yquant-circle, anchor=center, radius=.5mm`  
This style is used to draw the node for a control, both positive and negative.

`/yquant/every positive control` default: `fill=black`  
This style is installed for every positive control (i.e., one that conditions on the register being in state  $|1\rangle$  or 1).

`/yquant/every negative control` default: `draw`  
This style is installed for every negative control (i.e., one that conditions on the register being in state  $|0\rangle$  or 0).

`/yquant/every operator` default: `anchor=center`  
 This style is installed for every gate (and also pseudo-gates such as the `slash` operator) that acts on one or multiple registers.

`/yquant/every multi line` default: `draw, decoration={snake, amplitude=.25mm, segment length=5pt}, decorate` New in 0.1.2  
 This style is used to draw the vertical line that connects discontinuous slices of sub-gates.

`/yquant/this operator` default:  
 This style is appended to the current style installed for an operator; it should be used only locally to overwrite any global configuration effect.

`/yquant/this control` default:  
 This style is appended to the current style installed for a control; it should be used only locally to overwrite any global configuration effect.

`/yquant/operator style` default: `/yquant/this operator/.append style={#1}`  
 This is a shorthand that can be used to modify the appearance of the current operator.

`/yquant/control style` default: `/yquant/every control line/.append style={#1}, /yquant/this control/.append style={#1}`  
 This is a shorthand that can be used to modify the appearance of the current control and its associated line.

`/yquant/style` default: `/yquant/operator style={#1}, /yquant/control style={#1}`  
 This is a shorthand that modifies the appearance of both the current operator and any controls or control lines.

`/yquant/operator/multi as single` default: `/yquant/every multi line/.style=/yquant/every control line` New in 0.1.2  
 This style is automatically set for certain gates such as the `swap` or the `zz` gate. For those gates, neighboring registers will be treated as discontinuous; and this style will enforce their connecting line to have the style used by control lines. The default `/yquant/every multi line` is a wavy line; this allows to distinguish discontinuous multi-qubit gates from multiple single-qubit gates when using controls. Still, some gates have such an established appearance that—despite being logically misleading—we rather use the same style as for a control line.

- `/yquant/operator/if multi` default: `false` New in 0.4  
 This style can be invoked by other styles with an arguments that contains styles to be executed only if the current gate is used in a multi-register fashion. See [/yquant/every label](#) for an example.
- `/yquant/circuit/seamless` default: `false` New in 0.4  
 The value of this setting determines whether circuits drawn in a `yquant` environment in the current group will be drawn in a “seamless” state (hence, this style must be set *before* the `yquant` environment is started). The key [/yquant/operator/separation](#) will control the amount of padding with which a wire starts or ends before the first or after the last gate. By turning on the seamless state, this padding is suppressed. Using outputs or giving an initial value at the register declaration brings the corresponding padding back. Usually, this setting is intended only for subcircuits. Direct access is discouraged, as it will persist in subcircuits. Only access it via [/yquant/operators/subcircuit/seamless](#).
- `/yquant/every post measurement control` default: `indirect` New in 0.4  
 This style determines the default arrangement of measurements that are followed by positive controls.  
 The default option `indirect` will draw the measurement at the position where it is specified. Any later use of a control will be at the position of the controlled gate. The option `direct` will defer the measurement. If later on, a controlled operation is used where the positive controls contain all of the targets of this measurement *and* no other gate was executed meanwhile on any of the targets of this measurement, then the measurement gate will replace the corresponding positive control knobs (and might inherit `TikZ` options of the embedding gate); otherwise, it will behave as if the `indirect` option had been specified.  
 Some care must be taken when gates are named that are affected by this option. If the embedding gate is named, the positive controls that will be replaced by measurements are no longer available with the “p” suffix (but other positive controls will still be numbered as if all were). Attach the name to the measurement in order to access it as if it were an ordinary gate; however, note that the name only becomes available after the later embedding gate was called.  
 Note that this setting affects all measurements that have a compatible shape; currently, this is only `measure`. While there is no technical difficulty in implementing the same behavior for `dmeter`, its particular shape does not really suggest this use. However, if you desire to do so, please file a feature request.



### 3.5 Styles for operators

`/yquant/operators/every barrier` default: `shape=yquant-line, dashed, draw,` Changed in 0.4  
`shorten <= -1mm, shorten >= -1mm`

This style is installed for every `barrier` pseudo-gate, i.e., the one that is used to explicitly denote a separation between “before” and “after” within the circuit.

Note that the `shorten` keys are only present in the default style if you specify at least the compatibility version 0.4.

`/yquant/operators/every box` default: `shape=yquant-rectangle, draw,`  
`align=center, inner xsep=1mm, x radius=2mm, y radius=2.47mm`

This style is installed for every `box` operator.

`/yquant/operators/every custom gate` default: Changed in 0.4  
`/yquant/operators/subcircuit/seamless` New in 0.2

This style is by default installed for every user-defined gate. User-defined gates are implemented via subcircuits; this style suppresses the box that surrounds the subcircuit and by default suppresses all register names. This allows a seamless integration of the gate/subcircuit into the main circuit, without putting particular emphasis to the fact that what was defined as the custom gate indeed belongs together. Note that with the `compat` key set before 0.4, this style instead defaults to `/yquant/operators/subcircuit/frameless,` `/yquant/register/default name=.`

`/yquant/operators/every dmeter` default: `shape=yquant-dmeter, x`  
`radius=2mm, y radius=2mm, fill=white, draw`

This style is installed for every `dmeter` gate. The `yquant-dmeter` shape consists of a rectangle whose right side is replaced by a circle, resembling the letter “D.”

`/yquant/operators/every h` default: `/yquant/operators/every box`  
This style is installed for every `h` (Hadamard) operator.

`/yquant/operators/every inspect` default: `shape=yquant-output, align=left,`  
`outer xsep=.3333em, y radius=2.47mm, /yquant/operator/if`  
`multi={draw, decoration={gapped brace, raise=2pt}, decorate}`

This style is installed for every `inspect` gate. It does not have any shape on its own, apart from multi-register uses, in which it will contain a brace on its left.

`/yquant/operators/every measure` default: shape=yquant-measure, x radius=4mm, y radius=2.5mm, draw

This style is installed for every `measure` gate. The `yquant-measure` shape is a rectangle that contains a “meter” symbol. It allows for a text to be put inside (e.g., a basis), which then shifts the meter symbol accordingly.

`/yquant/operators/every measure meter` default: draw, `-{Latex[length=2.5pt]}`

This style is applied to the path that resembles the “meter” symbol that is drawn by the `yquant-measure` shape. Due to the default style, the `TikZ` library `arrows.meta` is automatically loaded with `yquant`.

`/yquant/operators/every not` default: shape=yquant-oplus, radius=1.3mm, draw

This style is installed for every `not` or `cnot` gate (which are synonyms, and actually do the same as the Pauli  $\sigma_x$  gate). The `yquant-oplus` shape resembles the addition-modulo-two symbol  $\oplus$ .

`/yquant/operators/every pauli` default: /yquant/operators/every box

This style is installed for every Pauli operator, i.e., `x`, `y`, and `z`.

`/yquant/operators/every phase` default: shape=yquant-circle, radius=.5mm, fill

This style is installed for every `phase` gate  $|0\rangle\langle 0| + e^{i\phi} |1\rangle\langle 1|$ .

`/yquant/operators/every slash` default: shape=yquant-slash, x radius=.5mm, y radius=.7mm, draw

This style is installed for every `slash` pseudo-gate, i.e., the one that is used to indicate that a single register line actually denotes multiple registers.

`/yquant/operators/every subcircuit` default: New in 0.2

This style is installed for every `subcircuit`. Note that all styles given here will also apply to every element in the subcircuit; in a way, this is an addition to `/yquant/every circuit` (which is also again put into effect at the beginning of a subcircuit).

`/yquant/operators/every subcircuit box` default: `/yquant/operators/every box` New in 0.2

This style is installed for every `subcircuit`. Note that in contrast to all other styles such as `/yquant/operators/every subcircuit` or `/yquant/this operator`, this style is only applied to the “container” node of the subcircuit, but not to the elements in the subcircuit themselves. Also note that the box style by default contains an `inner xsep` that will be added as an inside padding. This makes sense if your wires have labels so that these labels don’t move too closely to the border of the box. However, if you do not labelled wires but still want to have a box around the subcircuit, you should consider removing the separation—as it will be added to the initial wire padding given by `/yquant/operator/separation`.

`/yquant/subcircuit box style` default: `/yquant/operators/every subcircuit box/.append style={#1}` New in 0.2

This is a shorthand to append styles to the subcircuit box only.

`/yquant/operators/this subcircuit box` default: New in 0.2

This style is appended to the current style installed for the `subcircuit`, but will not apply to its contents. Additionally, this style will be reset to an empty style at the beginning of each subcircuit, so that it really only applies to exactly the subcircuit box it is explicitly specified on, not to nested subcircuit boxes.

`/yquant/this subcircuit box style` default: `/yquant/operators/this subcircuit box/.append style={#1}` New in 0.2

This is a shorthand to append styles to the current subcircuit box only.

`/yquant/operators/subcircuit/frameless` default: `/yquant/operators/this subcircuit box/.append style={draw=none, inner sep=0pt}` New in 0.4

This is a shorthand style that removes the frame and additional inner separation for the current subcircuit. Note that still, the wire padding given by `/yquant/operator/separation` is present within the—now invisible—outer box that contains the subcircuit (use `/yquant/operators/subcircuit/seamless` to suppress it). Hence, the most prominent application of this key is if the wires before and after the subcircuit are `nobits`, which provides a clean way to build up circuit equations with perfectly aligned wires (examples can be found in section 6).

`/yquant/operators/subcircuit/name mangling`      default: `prefix or discard`      New in 0.5

This option defines how named nodes within subcircuits are made available to the outer circuit:

- `prefix or discard`  
If the subcircuit itself has a name  $s$  and the inner gate has a name  $g$ , the outer circuit can refer to the inner gate via the name  $s-g$ . Note that  $s$  itself may not only consist of the user-specified name, but may instead already be suffixed by  $-0, -1, \dots$ , if the subcircuits were assigned to multiple targets.  
If the subcircuit itself has no name, works as `discard`.
- `prefix or transparent`  
If the subcircuit itself has a name, as works as `prefix or discard`; else, works as `transparent`.
- `transparent`  
The inner gates are always available in the outer circuit by their original names. Note that this may potentially lead to naming conflicts, which are always resolved by the latest name overwriting all previous declarations without notice.
- `discard`  
The inner gates will not be available in the outer circuit.

Note that if a new gate is defined via `\yquantdefinegate`—which internally uses subcircuits—the value of this option at the time of declaration is the relevant one, not the one at the time of usage. This can be influenced via `/yquant/operators/subcircuit/name mangling reset`.

`/yquant/operators/subcircuit/name mangling reset`      default: `true`      New in 0.5

The current value of `/yquant/operators/subcircuit/name mangling` will be reset at the beginning of a subcircuit to the value it had upon declaration of the subcircuit only if this option is `true` upon *using* the subcircuit (which typically will only make a difference if the subcircuit was defined via `\yquantdefinegate` at some earlier stage).



Setting this value to `false` has the potential of breaking the corresponding subcircuit/custom gate, as it may internally reference gates by names that are no longer the correct ones. Do not use this property without a very good reason and thorough understanding of what is happening.

`/yquant/operators/subcircuit/seamless` default: `/yquant/operators/subcircuit/frameless, /yquant/register/default name=, /yquant/circuit/seamless` New in 0.4

This option carries out multiple actions that are responsible to let the current subcircuit appear in a “seamless” state:

- It calls `/yquant/operators/subcircuit/frameless`.
- It sets `/yquant/circuit/seamless` to true.
- It ensures that `/yquant/circuit/seamless` is reset within the subcircuit, so that it does not propagate to nested subcircuits.

`/yquant/operators/every swap` default: `shape=yquant-swap, radius=.75mm, draw`

This style is installed for every `swap` gate that interchanges two qubits. The `yquant-swap` shape consists of a single cross.

`/yquant/operators/every wave` default: `shape=yquant-circle, radius=.5mm, fill` New in 0.1.2

This style is installed for every `correlate` gate.

`/yquant/operators/every x` default: `/yquant/operators/every pauli`

This style is installed for every Pauli operator  $\sigma_x$ , i.e., `x`.

`/yquant/operators/every xx` default: `shape=yquant-rectangle, radius=.75mm, draw`

This style is installed for every `xx` gate in symmetrized notation ( $|++\rangle\langle++| + |+-\rangle\langle+-| + |-+\rangle\langle-+| + |--\rangle\langle--|$ ).

`/yquant/operators/every y` default: `/yquant/operators/every pauli`

This style is installed for every Pauli operator  $\sigma_y$ , i.e., `y`.

`/yquant/operators/every z` default: `/yquant/operators/every pauli`

This style is installed for every Pauli operator  $\sigma_z$ , i.e., `z`.

`/yquant/operators/every zz` default: `shape=yquant-circle, radius=.5mm, fill`

This style is installed for every `zz` gate (aka CPHASE) in symmetrized notation ( $|00\rangle\langle00| + |01\rangle\langle01| + |10\rangle\langle10| - |11\rangle\langle11|$ ).

## 4 Doing the impossible

`yquant` will almost certainly never be able to do everything an author has in mind. Sometimes, there is the need to draw something non-standard, and this cannot be implemented in the `yquant` language. However, since `yquant` is a layer on top of `TikZ`, it should be very hard to find something (meaningful) that cannot be done by combining the power of both packages.

### 4.1 Mixing `yquant` and `TikZ` code

Before or after any gate, you may interrupt the `yquant` instructions to perform arbitrary `TikZ` path operations. After every such operation, `yquant` will automatically restart its parser so that you can fluently jump between `yquant` and `TikZ` code. You can even interject arbitrary  $\text{\TeX}$  code (or, say, low-level `pgf` commands); however, then, `yquant` is not able to restart its parser. For this reason, after the last command in a block of  $\text{\TeX}$  commands, you must issue `\yquant`, which then re-enables the `yquant` language.

### 4.2 Accessing gates in `TikZ`

The feature to perform arbitrary `TikZ` operations is powerful in itself, but would be of limited use were there no way to access the elements in the quantum circuit. `yquant` provides a global attribute name that can be assigned to every gate. All quantum operations are in fact `TikZ` nodes, and the name you give to them then becomes a `TikZ` name, which you can easily reference to get the coordinates of a particular operator. Note that the name you specify is only available if a single register is targeted. The name is suffixed by `-\idx`, where `\idx` refers to the (zero-based) index of the operation ordered from top to bottom (i.e., if an operator acts on two qubits and should be named `op`, the topmost operator will be available as `op-0` and the second as `op-1`). Multiple slices in a discontinuous multi-register are additionally suffixed by `-s<slice index>`. All controls are also named, suffixed by `-p\idx` or `-n\idx` for positive and negative controls (i.e., the topmost positive control of the previous operator will be available as `op-p0`). Counters for target registers, positive, and negative controls are all independent. Finally, you can even access names within a subcircuit, provided you give a name to the subcircuit. All nodes in the subcircuit will then have the name `<subcircuit name>-\name specified in the subcircuits>`. Note that here, `<subcircuit name>` is the full name of the subcircuit, which includes the `-\idx` suffix, unless there is only a single target register. For nested subcircuits, you will get multiple prefixes. The

New in 0.4.1  
New in 0.5

prefixing behavior can be influenced by `/yquant/operators/subcircuit/name mangling`.

### 4.3 Shapes and the drawing pipeline

All `yquant` shapes have the anchors available you would typically expect from a `TikZ` shape of the given outline. The `center` anchor will be aligned to the wire. In addition to the normal paths implemented by `TikZ` shapes, those fit for `yquant` must additionally implement clipping paths, a `yquant` addition to `TikZ` shapes. Such a path has to provide the “clipping outline,” i.e., anything that should not contain register or control lines. There may be a difference between horizontal and vertical clipping outlines. To understand clipping paths, `yquant`’s drawing pipeline needs to be explained.

Changed in 0.1.2

- In a first run—this is what happens directly at the position where you type the gate command—`yquant` will “virtually” draw the gates in order to determine their dimensions and calculate register heights. The actual drawing commands are written to a macro (this is the cause that some macros must be preceded by `\protect` if used in a gate value—in fact, if multiple registers are targeted in one gate, the style and values required for this gate are only stored once, so that for example `\idx` is a `\protected` macro until the very end).
- Deferred gates (measurements that may replace future control knobs) are stored temporarily and queried when the next gate is executed or at the end of the circuit. The corresponding commands—either re-inserting if they must appear at their original position or substituting the controls—are inserted appropriately.
- When `\end{yquant}` is encountered, the vertical positions are determined and the actual drawing commands are executed.
- Unless the operation changes the wire type or style, do the following (first two items for every register at which an operator node has to be created).
  - Create the operator node at the appropriate position.
  - Call `\pgfshapeclippath` on the newly created node. This will first determine whether the node was stroked; if not, `\pgflinewidth` is set to zero. Then, it will call the horizontal clipping path, which is supposed to create some soft path commands. Those soft path commands are collected in a macro on a per-register basis and the soft path is cleared.

New in 0.4

The same happens for the vertical clipping path, which is collected in a macro on a per-operation basis.

- If control lines or multi lines are to be drawn, the vertical clipping path commands are now executed and installed as an inverted<sup>1</sup> clipping.
- Control lines and multi lines are drawn (in this order) from one to the next center anchor. Due to the clipping commands, this will create a perfect connection with the shape of the gate, but even transparent gates are possible without the lines being visible.
- If the operation changes the wire type or style, or if there is no operation left on this register, the following is done.
  - Load the clipping paths accumulated for all the gates acting on this register and install the inverted clipping.
  - Draw the wire as one continuous line from where the last wire ended (or the beginning of the circuit) to the center of the last gate, or to the common end position for all wires of the circuit.
  - Remove the clipping paths stored so far on this register, apart from the clipping on the last gate (which will be needed again if this was not the end of the circuit).

#### 4.4 Overwriting the height and depth calculation

`yquant` automatically takes care of calculating the height and depth of all registers, so that their final vertical positions are chosen without overlap. This is almost always advisable, but it has some weaknesses:

- If you specify a multi-register gate, say, extending for three registers and this requires a certain height and depth, where should this be accounted for? `yquant` is able to handle these situations by first determining all heights and depths that can safely be attributed to individual registers. After that, it checks for all multi-register gates: Is the space from the top of the first to the bottom of the last register enough to hold the multi-qubit gate? If not, it evenly distributes the additional required space to all registers that are visually within the range of this multi-register.

New in 0.4

---

<sup>1</sup>Inverting the clipping means that instead of drawing only *within* the clipping path (which corresponds to the gates), we only draw *outside*. However, as there is no direct support for this, we invert by exploiting the even-odd rule. If you specify a register multiple times, whether as target, control, or mixed, funny effects can be expected, as the clipping region is inverted multiple times. Note that using a register more than once is always an error, but `yquant` does not check for it due to the high overhead.



This will fail to produce good results (hopefully) only in two cases:

- If you place labels on the gate, those are outside of the gate—and typically, either below or above. Hence, the additional extent stemming from them should *not* be equally distributed among all registers, but either to the height of the first or the depth of the last one. Currently, `yquant` is unable to detect this (and, considering the fact that you can place labels at any angle, this is not an easy problem to solve except for special cases).
- If you make use of a discontinuous `init` gate with a large vertical extent, `yquant` will correctly allocate space as if the gate’s content were placed in the vertical center. However, if there is no way to put the arch of the brace at the middle, as the register at this position is excluded from the gate, the content will be shifted—but only after calculating the extent. Hence, the automatically calculated vertical positions will be unsuitable.
- Sometimes, there is more space available than `yquant` thinks because you already discarded some wire. `yquant` does not keep track of whether the wires below or above a gate are actually visible at this position—which is not even be known at the time the gate command is issued, as horizontal positions are determined only in the drawing stage. Hence, you may choose to draw “within” the other, invisible wire.

In these certain special cases, you may want to turn off the automatic calculation for one particular gate. Note that you may then, depending on the situation, obtain results with overlapping gates. You can use the keys `/yquant/register/minimum height` and `/yquant/register/minimum depth` when declaring the relevant register to manually specify a larger desired value, but you have to experiment with regard to what this value is.

New in 0.4

The global attribute `overlay` (conveniently overshadowing `TikZ`’s `overlay` key, which should not be used for gates) can take the values

- `true` (default if no value given, combines `multi`, `height`, and `depth`),
- `multi` (short `m`),
- `height` (short `ht`, `h`),
- `depth` (short `dp`, `d`),
- `single` (short `s`, combines `height` and `depth`), and

- `false` (useless, default if attribute not given).

It disables the calculation of the selected vertical extent for this particular gate. (In fact, `multi`, `height`, `depth`, and `single` are subkeys that accept boolean values.)

## 5 Reference: Gates and operations

This section lists all operations `yquant` currently understands. It also details all arguments that can be given to customize the operation, apart from name and overlay, which are always available. Note that the `[value=<value>]` attribute can (and should) alternatively be given as a braced expression that follows the name of the register.

New in 0.4

### 5.1 `addstyle`

New in 0.1.2

Syntax: `setstyle <target>;`

This is an invisible pseudo-gate that immediately changes the `TikZ` style with which the register lines of all target registers are drawn. It adds to the styles that are already installed. Use `setstyle` to replace styles. It may not span multiple registers and does not allow for controls.

*Possible attributes:*

- `[value=<styles>]` (required)  
Denotes the new styles; this should be a string that could be passed to `\tikzset`.

### 5.2 `align`

Syntax: `align <target>;`

This is an invisible pseudo-gate that enforces all affected registers to share a common horizontal position for their next gate, which is determined by the largest position of all gates involved. It may not span multiple registers and does not allow for controls. The gate now always aligns the wires, i.e., if they are discarded directly after this gate, they will still be discarded all at the same position.

Changed in 0.4

*Possible attributes:* none

### 5.3 `barrier`

Syntax: `barrier <target>;`

This is a pseudo-gate that denotes some physical barrier that ensures execution with a specific timing; it is basically a visible version of the `align` gate, denoted by a vertical line. It may span multiple registers, but does not allow for controls. The style `/yquant/operators/every barrier` is installed.

*Possible attributes:* none

## 5.4 box

Syntax: `box <target> | <pcontrol> ~ <ncontrol>;`

This is a generic register of a rectangular shape that can be filled with arbitrary content. It may span multiple registers and allows for controls. The style `/yquant/operators/every box` is installed.

*Possible attributes:*

- `[value=<value>]`  
Denotes the content of the box.

## 5.5 cbit

Syntax: `cbit <name>[<len>;`

Declares a register of type `cbit`.

*see `qubit`*

## 5.6 correlate

New in 0.1.2

Syntax: `correlate <target>;`

This is a pseudo-gate that indicates a correlation (usually a Bell-state) present between the multi-registers involved. This gate should span multiple registers and does not allow for controls.

*Possible attributes:* none

## 5.7 cnot

Syntax: `cnot <target> | <pcontrol> ~ <ncontrol>;`

This is a synonym for the `not` gate. Note that despite its name, controls are not mandatory and also here, the style `/yquant/operators/every not` is installed.

## 5.8 discard

Syntax: `discard <target>;`

This is an invisible pseudo-gate that changes the type of all target registers to `nobit`, i.e., no line will be drawn for them. This has effect already for the outgoing line of the last gate on the target registers. The gate may not span multiple registers and does not allow for controls. To change a register type on-the-fly into something different from `nobit`, use the `settype` pseudo-gate.

Changed in 0.1.2

*Possible attributes:* none

## 5.9 dmeter

Syntax: `dmeter <target>;`

This is a measurement gate, denoted by a “D” shape. It changes the type of all targets involved. It may span multiple registers, but does not allow for controls. The style `/yquant/operators/every dmeter` is installed.

*Possible attributes:*

- `[value=<value>]`  
Allows to specify a text that will be included inside the gate, possible enlarging its width. For outside texts, use `TikZ` labels instead.
- `[type=<qubit|cbit|qubits>]`  
Allows to specify the type into which the affected targets are converted. Default is `cbit`.

## 5.10 h

Syntax: `h <target> | <pcontrol> ~ <ncontrol>;`

This is a Hadamard gate,  $(|0\rangle\langle 0| + |0\rangle\langle 1| + |1\rangle\langle 0| - |1\rangle\langle 1|) / \sqrt{2}$ , denoted by a rectangle that contains the letter  $H$ . It may not span multiple registers, but allows for controls.

The style `/yquant/operators/every h` is installed.

*Possible attributes:* none

## 5.11 hspace

Syntax: `hspace <target>;`

This is an invisible pseudo-gate that inserts a certain amount of white space into all target registers. It may not span multiple registers and does not allow for controls. The gate now always has an effect, e.g., if the wire is discarded after this gate, it will still be extended by the given amount first.

Changed in 0.4

*Possible attributes:*

- `[value=<dim>]` (required)  
Gives the amount of white space that is to be inserted. Must be a valid (nonnegative)  $\text{\TeX}$  dimension.

## 5.12 init

Changed in 0.4

Syntax: `init <target>;`

This is a pseudo-gate that (re)initializes a registers to a given state. It may span

multiple registers, but does not allow for controls. The style `/yquant/every label` is installed. Note that this pseudo-gate, unlike all others, behaves differently if it is the first operation acting on a register: in this case, it does not increment the horizontal position, but uses the space available to the left; and the style `/yquant/every initial label` is installed additionally. Internally, creating a new register with some printed name is translated into the creation of an unnamed register, followed by application of this gate with the desired text.

*Possible attributes:*

- `[type=<qubit|cbit|qubits>]`  
Allows to specify the type into which the affected target registers are converted. Default is the type of the first target register that is different from `nobit`, or `qubit` if they all are `nobit`. The style `/yquant/every <type> label` is installed additionally.
- `[value=<value>]` (required)  
Denotes the label that is printed to the left of the wire.  
Inside the value, `\idx` expands to the current index within the register list.

### 5.13 inspect

New in 0.4

Syntax: `inspect <target>;`

This is a pseudo-gate that allows to print the current state of one or multiple registers within a circuit. It may span multiple registers, but does not allow for controls. The style `/yquant/every inspect` is installed. Essentially, it is the same as an `output` gate that will be drawn immediately at the current position and not deferred until the end.

*Possible attributes:*

- `[value=<value>]` (required)  
Denotes the text that is to be printed. Inside the value, `\idx` expands to the current index within the register list.

### 5.14 measure

Changed in 0.4

Syntax: `measure <target>;`

This is a measurement gate, denoted by a rectangle with a meter symbol. It changes the type of all targets involved. It may span multiple registers, but does not allow for controls. The style `/yquant/operators/every measure` is installed. It may be deferred to be used instead of a control knob for a later gate using

the `/yquant/every post measurement control` style or the suitable attributes; see the documentation for this style.

*Possible attributes:*

- `[type=<qubit|cbit|qubits>]`  
Allows to specify the type into which the affected targets are converted. Default is `cbit`.
- `[value=<value>]`  
Allows to specify a text that will be included at the bottom of the rectangle (which will shift the meter symbol upwards accordingly). For outside texts, use `TikZ` labels instead.
- `[direct control]`  
Temporarily sets `/yquant/every post measurement control=direct` for this particular gate.
- `[indirect control]`  
Temporarily sets `/yquant/every post measurement control=indirect` for this particular gate.

### 5.15 nobit

Syntax: `nobit <name>[<len>];`

Declares a register of type `nobit`. The `<name>` must be a self-chosen name for the register which was not previously used as a register name in this circuit (but names can be re-used in subcircuits). Names are case-insensitive. The register can be made into a vector register by specifying `<len>` (default 1).

*Possible attributes:*

- `[out]` or `[ancilla]` (required in subcircuits)  
*see `qubit`*

New in 0.2

### 5.16 not

Syntax: `not <target> | <pcontrol> ~ <ncontrol>;`

This is a NOT gate,  $|0\rangle\langle 1| + |1\rangle\langle 0|$ , denoted by the  $\oplus$  symbol. It may not span multiple registers, but allows for controls. Due to its common usage, the synonymous gate `cnot` is provided. The style `/yquant/operators/every not` is installed.

*Possible attributes:* none

## 5.17 output

Changed in 0.4

Syntax: `output <target>;`

This is a pseudo-gate that allows to write some text at the very end of the register line. It may only be specified once per register. It may span multiple registers, but does not allow for controls. The style `/yquant/every output` is installed, and also the style `/yquant/every <type> output`, where `<type>` is the type of the affected register (at the time of printout).

*Possible attributes:*

- `[value=<value>]` (required)  
Denotes the text that is to be printed. Inside the value, `\idx` expands to the current index within the register list.

## 5.18 phase

Syntax: `phase <name> | <pcontrol> ~ <ncontrol>;`

This is a phase gate,  $|0\rangle\langle 0| + e^{i\phi} |1\rangle\langle 1|$ , denoted by a filled circle. It may not span multiple registers, but allows for controls. The style `/yquant/operators/every phase` is installed.

*Possible attributes:*

- `[value=<value>]` (required)  
Denotes the angle  $\phi$  that is to be printed together with the gate. Position and appearance can be influenced by setting the position of `TikZ` labels, as this is internally used. Note that at the moment, it is not possible to change any label options on a gate-type basis, only locally or fully globally (`TikZ` feature request [#811](#)).

## 5.19 qubit

Syntax: `qubit <name>[<len>;`

Declares a register of type qubit. The `<name>` must be a self-chosen name for the register which was not previously used as a register name in this circuit (but names can be re-used in subcircuits). Names are case-insensitive. The register can be made into a vector register by specifying `<len>` (default 1).

*Possible attributes:*

- `[after=<regname>]`  
If given, the register will start not at the left of the circuit but instead at the position at which the last gate in the register `<regname>` ended.  
This attribute may not be given in combination with `[in]` or `[inout]`.



- `[in]`, `[out]`, `[inout]`, or `[ancilla]`

New in 0.2

Default: `[ancilla]` for top-level circuits (do not change there); `[inout]` for subcircuits.

Determines how a subcircuit interacts with its parent circuit.

Registers declared with the `[ancilla]` attribute are available only to the subcircuit; they cannot be connected to an outside wire.

Registers declared with the `[in]` or `[inout]` attribute will expect an outer wire of the same type to be present and will then be identical with this outer wire. Any changes applied to the wire within the subcircuit automatically also happen on the associated outer wire. If the attribute is `[in]`, the wire will automatically be discarded at the end of the subcircuit (and hence also in the outer circuit, where it may be re-initialized). This is different from applying the `discard` gate in that the wire will still extend until the end of the subcircuit and may thus receive proper `outputs`.

Registers declared with the `[out]` attribute will expect a discarded outer wire to be present, which will be initialized to a qubit at the beginning of the subcircuit, and from then on be identical with the outer wire.

- `[value=<value>]`

Denotes the label that is printed to the left of the wire. If the value is omitted, the default is used (`/yquant/register/default name`, preinitialized to `\regidx`).

Inside the value, `\reg` expands to `<name>`, `\len` expands to `<len>`, `\idx` expands to the current index within the vector register ( $0 \leq \text{\code{\idx}} < \text{\code{\len}}$ ), and `\regidx` expands to `\reg` if `<len>` is one, or to `\reg[\idx]` else.

## 5.20 qubits

Syntax: `qubits <name>[<len>];`

Declares a register of type qubits.

see *qubit*

## 5.21 setstyle

New in 0.1.2

Syntax: `setstyle <target>;`

This is an invisible pseudo-gate that immediately changes the `TikZ` style with which the register lines of all target registers are drawn. It replaces all previous styles. Use `addstyle` to accumulate styles. It may not span multiple registers and does not allow for controls.

*Possible attributes:*

- [value=<styles>] (required)  
Denotes the new styles; this should be a string that could be passed to `\tikzset`.

## 5.22 `settype`

New in 0.1.2

Syntax: `settype <target>;`

This is an invisible pseudo-gate that immediately changes the type of the targets registers, taking effect with the output line extending from the last drawn gate. It may not span multiple registers and does not allow for controls.

*Possible attributes:*

- [value=<qubit|cbit|qubits>] (required)  
Denotes the new type that is assigned to all registers. To change the type to `nobit`, use the `discard` pseudo-gate instead.

## 5.23 `setwire`

Removed in 0.4

Deprecated in 0.1.2

Use `settype` instead.

This gate is only available if a compatibility version before 0.4 is chosen.

## 5.24 `slash`

Syntax: `slash <target>;`

This is a pseudo-gate used to denote that a single line actually represents multiple registers. It is drawn as a short slash through the line of the register. Note that this gate, in contrast to all others, is positioned on the line extending from the last gate or the initialization line of the registers and does not advance the register's horizontal position. The style `/yquant/operators/every slash` is installed.

*Possible attributes:* none

## 5.25 `subcircuit`

New in 0.2

Syntax: `subcircuit <target>;`

This is a subcircuit gate which inserts independent quantum circuits at the current position within the circuit. It may span multiple registers, but is never split into contiguous slices. It allows for controls and may change the type of any target involved, depending on the particular subcircuit. The style `/yquant/operators/every subcircuit` is installed.

*Possible attributes:*

- `frameless` New in 0.4  
This `/yquant/operators/subcircuit/frameless` style is activated with this shorthand.
- `name mangling` New in 0.5  
This shorthand will pass the value of the attribute directly to the configuration key `/yquant/operators/subcircuit/name mangling`.
- `seamless` New in 0.4  
The `/yquant/operators/subcircuit/seamless` style is activated with this shorthand (implies `frameless`).
- `value=<subcircuit>` (required)  
Denotes the content of the subcircuit. It is specified in the usual syntax of `yquant`. Note that, regardless of the outer environment, a subcircuit always implicitly uses the unstarred form, i.e., you must declare every register explicitly before its first usage. This is to make sure that the interface of the circuit, i.e., which registers are taken as input and/or output parameters and in which order, is not accidentally mistaken.

The mapping between input and output registers is trivial for single-qubit uses. For multi-qubit uses, it works in the following way—in short, it matches in visual order. You declare input and output registers by using the appropriate attributes on the `qubit`, `cbit`, `qubits` (or even `nobit`) gates. The list of all non-ancillas, from the topmost to the bottom-most, forms the list of parameter registers of the subcircuit. This is exactly the number of registers that must be supplied within one multi-qubit target. Also within the multi-qubit target, we sort all registers from the topmost to the bottom-most (in the order as they visually appear, not the order in which they are entered). Those two lists of equal length are then mapped 1 : 1 to each other. Intermixing with ancillas is possible at every position and will lead to a vertical shift of the wires, until all registers, inner and outer, can be displayed flawlessly.

As subcircuits follow the same rules as ordinary circuits, it is possible to mix them with arbitrary  $\text{\TeX}$  code, and also to access named gates within the subcircuit—but note that named gates in the outer circuit cannot be accessed (at least unless you play with the `name prefix` key in `TikZ`). In order to access inner nodes from the outer circuit, the subcircuit itself must be named; the inner nodes are then prefixed by the name of the subcircuit and a dash.

It is possible to nest subcircuits arbitrarily.

## 5.26 swap

Syntax: `swap <targets> | <pcontrol> ~ <ncontrol>;`

This is the two-qubit SWAP gate  $|00\rangle\langle 00| + |01\rangle\langle 10| + |10\rangle\langle 01| + |11\rangle\langle 11|$  that exchanges two qubits. It is denoted by crosses at the affected registers which are connected by a control line. It may span multiple registers (in fact, it should always span exactly two registers, though `yquant` does not enforce this), and it allows for controls. However, refrain from combining *multiple* two-qubit targets *together* with controls. The control line will extend from the first to the last of all registers involved in the operation, so that it is impossible to discern visually which registers should actually be swapped. Using multiple swaps without controls in one operation is fine, as well as a single controlled swap. The style `/yquant/operators/every swap` is installed.

*Possible attributes:* none

## 5.27 x

Syntax: `x <target> | <pcontrol> ~ <ncontrol>;`

This is a Pauli  $\sigma_x$  gate  $|0\rangle\langle 1| + |1\rangle\langle 0|$ , denoted by a rectangle that contains the letter X. It may not span multiple registers, but allows for controls.

The style `/yquant/operators/every x` is installed.

*Possible attributes:* none

## 5.28 xx

Syntax: `xx <targets>;`

This is a symmetric flip gate, denoted by joined open squares. It should span multiple registers and it allows for controls. The same warnings as for the `swap` gate apply. The style `/yquant/operators/every xx` is installed.

*Possible attributes:* none

## 5.29 y

Syntax: `y <target> | <pcontrol> ~ <ncontrol>;`

This is a Pauli  $\sigma_y$  gate  $-i|0\rangle\langle 1| + i|1\rangle\langle 0|$ , denoted by a rectangle that contains the letter Y. It may not span multiple registers, but allows for controls.

The style `/yquant/operators/every y` is installed.

*Possible attributes:* none

### 5.30 **z**

Syntax: `z <target> | <pcontrol> ~ <ncontrol>;`

This is a Pauli  $\sigma_z$  gate  $|0\rangle\langle 0| - |1\rangle\langle 1|$ , denoted by a rectangle that contains the letter  $Z$ . It may not span multiple registers, but allows for controls.

The style `/yquant/operators/every z` is installed.

*Possible attributes:* none

### 5.31 **zz**

Syntax: `zz <targets>;`

This is a symmetric phase gate, denoted by joined filled circles. It should span multiple registers, but does not allow for controls. The same warnings as for the `swap` gate apply. The style `/yquant/operators/every zz` is installed.

*Possible attributes:* none

## 6 Examples

This section will contain lots of examples. On the left-hand side, the output is given, while the code to construct the example is on the right. All examples that are provided originate from the examples supplied with `qasm`, `qcircuit`, and `quantikz`. We will essentially follow their manuals example-by-example, which gives a nice comparison in how to achieve the given feature using these packages and `yquant` instead. All examples of course require inclusion of the `yquant` package with newest compatibility in the preamble, and some also require `braket`.

### 6.1 `qasm` documentation

The `qasm` documentation most often names the registers in the way  $|\text{register}_{\text{index}}\rangle$ . This can be achieved by writing

```
qubit { $\$ \backslash \text{ket}\{<\text{name}>_{\backslash \text{idx}}\} \$$ } <name>[<len>];
```

but if you want to realize this naming scheme for all circuits in your document, it is more convenient to say

```
\yquantset{register/default name= $\$ \backslash \text{ket}\{\backslash \text{reg}_{\backslash \text{idx}}\} \$$ }
```


in the preamble, as is done here.

Note that `yquant` also directly supports the `qasm` syntax, see section 7.2.

New in 0.3



#### test1 (create an EPR pair)




```
\begin{tikzpicture}
  \begin{yquant}
    qubit q[2];

    h q[0];
    cnot q[1] | q[0];
  \end{yquant}
\end{tikzpicture}
```



### test2 (simple teleportation circuit)

Updated in 0.1.1




```
\begin{tikzpicture}
\begin{yquant}
qubit q[3];

h q[1];
cnot q[2] | q[1];
cnot q[1] | q[0];
h q[0];
measure q[0-1];

z q[2] | q[1];
x q[2] | q[0];
\end{yquant}
\end{tikzpicture}
```



### test3 (swap circuit)




```
\begin{tikzpicture}
\begin{yquant}
qubit q[2];

cnot q[1] | q[0];
cnot q[0] | q[1];
cnot q[1] | q[0];
\end{yquant}
\end{tikzpicture}
```



#### test4 (quantum fourier transform on three qubits)

Updated in 0.1.1




```
\begin{tikzpicture}
\begin{yquant}
qubit j[3];

h j[0];
box {$S$} j[0] | j[1];
box {$T$} j[0] | j[2];
h j[1];
box {$S$} j[1] | j[2];
h j[2];
swap (j[0, 2]);
\end{yquant}
\end{tikzpicture}
```



#### test5 (demonstrate arbitrary qubit matrix ops)



```
% \usepackage{amsmath}
\begin{tikzpicture}
\begin{yquant}
qubit j[2];


box {$\begin{bmatrix} \cos\theta & -\sin\theta \\ \sin\theta & \cos\theta \end{bmatrix}$} j[1] | j[0];
box {$\begin{bmatrix} e^{i\alpha} & 0 \\ 0 & e^{-i\alpha} \end{bmatrix}$} j[0];
\end{yquant}
\end{tikzpicture}
```





### test6 (demonstrate multiple-qubit controlled single-q-gates)

Updated in 0.1.1




```
\begin{tikzpicture}
\begin{yquant}
qubit j[4];

cnot j[2] | j[0, 1];
x j[0];
box  $\{U\}$  j[1] | j[0, 2-3];
h j[2];
measure j[3];
\end{yquant}
\end{tikzpicture}
```



### test7 (measurement of operator with correction)

Updated in 0.1.1




```
\begin{tikzpicture}
\begin{yquant}
qubit q[2];

h q[0];
box  $\{U\}$  q[1] | q[0];
h q[0];
measure q[0];
box  $\{V\}$  q[1] | q[0];
\end{yquant}
\end{tikzpicture}
```



## test8 (stage in simplification of quantum teleportation)

Updated in 0.4



```
\begin{tikzpicture}
\begin{yquant}
qubit {\ket{q_0} = \ket{\psi}}
  \hookrightarrow q[1];
qubit {\ket{q_{\idx}} = \ket{0}}
  \hookrightarrow q[+2];

h q[1];
cnot q[1] | q[0];
cnot q[2] | q[1];
cnot q[1] | q[0];
h q[0];
cnot q[2] | q[1];
z q[0] | q[2];
\end{yquant}
\end{tikzpicture}
```

Note that we left out two Hadamards at the end.


Another way to provide various initial values in a single command is by performing case discrimination on `\idx`, for example in the following manner:

```
qubit {\ket{q_{\idx}} = \Ifcase\idx\relax \ket{\psi} \Else \ket{0} \Fi}
  \hookrightarrow q[3];
```

In principle, all  $\text{\TeX}$  conditionals that check against `\idx` need to be prefixed by `\protect`. If the `compat` key is at least 0.4, `yquant` will make the commands `\Ifnum`, `\Ifcase`, `\Or`, `\Else`, `\Fi`, `\Unless` and `\The` available for use within gates; they correspond in a certain way to auto-`\protected` versions of the corresponding  $\text{\TeX}$  primitives. Most likely, you will never need them inside values if not in the exact combination with `\idx`.



### test9 (two-qubit gate circuit implementation of Toffoli)




```
\begin{tikzpicture}
\begin{yquant}
qubit q[3];

box {\sqrt{X}} q[2] | q[1];
cnot q[1] | q[0];
box {\sqrt{X}^\dagger} q[2] |
  \hookrightarrow q[1];
cnot q[1] | q[0];
box {\sqrt{X}} q[2] | q[0];
\end{yquant}
\end{tikzpicture}
```



### test10 (multi-qubit gates also demonstrates use of classical bits)



```
\begin{tikzpicture}
\begin{yquant}
qubit {\ket{q_0}} q;
cbit {\c_1} c;
qubit {\ket{q_2}} q[+1];

h q[0];
box {\$U\$} (q[0], c);
box {\$S\$} q[1];
box {\$U\$} (c, q[1]);
\end{yquant}
\end{tikzpicture}
```


Instead of a discontinuous vector register, we could also have used three scalar registers. The labels chosen for `qasm` do not fit well to the indices `yquant` assigns. We might also have used a three-register vector and used the `settype` pseudo-gate to immediately change the second register into a classical one, which would give indices matching the labels—but still, the registers would have a common name, which would make this a very unnatural approach.

Alternative in 0.1.2  
Updated in 0.1.1



### test11 (user-defined multi-qubit ops)

Updated in 0.1.1



```
\begin{tikzpicture}
\begin{yquant}
qubit q[3];


h q[0];
box {$U_{f(x)}$} (q[0, 1]);
h q[1];
box {$U_{f(x, y)}$} (q);
\end{yquant}
\end{tikzpicture}
```

Here we used the fact that a vector register can also be addressed as a whole. Instead of (q), we could have also written, e.g., (q[0]-q[2]) or (q[0-2]), or enumerated all sub-registers in a comma-separated list.



### test12 (multi-qubit controlled multi-qubit operations)

Updated in 0.1.1




```
\begin{tikzpicture}
\begin{yquant}
qubit q[3];

h q[0];
box {$U$} (q[1-2]) | q[0];
h q[0];
box {$V$} (q[0-1]) | q[2];
\end{yquant}
\end{tikzpicture}
```



### test13 (three-qubit phase estimation circuit with QFT and controlled-U)



```


\begin{tikzpicture}
\begin{yquant}
qubit {\ket{j_{\idx}}} = \ket{0} j[3];
qubit s[2];

h j;
box {\$U^4\$} (s) | j[0];
box {\$U^2\$} (s) | j[1];
box {\$U\$} (s) | j[2];
h j[0];
box {\$S\$} j[1] | j[0];
h j[1];
box {\$T\$} j[2] | j[0];
box {\$S\$} j[2] | j[1];
h j[2];
measure j;
\end{yquant}
\end{tikzpicture}

```



### test14 (three-qubit FT QEC circuit with syndrome measurement)



```

\begin{tikzpicture}
  \begin{yquant}
    qubit q[3];
    qubit {\ket{s_{\idx}}} = \ket{0} s[2];
    cbit {\c_{\idx}} = 0 c[2];

    h s[0];
    cnot s[1] | s[0];
    cnot s[0] | q[0];
    cnot s[1] | q[1];
    cnot s[1] | s[0];
    h s[0];
    measure s;
    cnot c[0] | s[0];
    cnot c[1] | s[1];
    discard s; % to suppress wires extending until re-initialization

    init {\ket{0}} s;
    h s[0];
    cnot s[1] | s[0];
    cnot s[0] | q[1];
    cnot s[1] | q[2];
    cnot s[1] | s[0];
    h s[0];
    measure s;


    box {Process\\Syndrome} (s, c);
    box {\symcal R} (q) | s, c;
  \end{yquant}
\end{tikzpicture}

```



### test15 (“D-type” measurement)

Updated in 0.1.1




```
\begin{tikzpicture}
\begin{yquant}
qubit {\ket{q_0} = \ket{\psi}} q;
qubit {\ket{q_1} = \ket{+}} q[+1];

zz (q);
dmeter {\$H Z_\theta\$} q[0];
\end{yquant}
\end{tikzpicture}
```



### test16 (example from Nielsen paper on cluster states)

Updated in 0.4,  
0.1.2, 0.1.1



```
\begin{tikzpicture}
\begin{yquant}
qubit {\ket{q_{\idx}} = \ket{\psi}}
  \hookrightarrow q[2];
qubit {\ket{q_2} = \ket{\phi}} q[+1];
qubit {\ket{q_3} = \ket{0}} q[+1];


zz (q[1], q[2]);
align q;
cnot q[3] | q[2];
slash q[0];
dmeter q[3];
align q;
[solid]
barrier q[2];
discard q[2];
\end{yquant}
\end{tikzpicture}
```

We needed to include an `align` pseudo-gate to put the slash at the desired position. Usually, this would be sufficient to put the `cnot` and the `slash` gate directly under each other, as it is in the `qasm` example. However, the `slash` gate is special in that it does not need horizontal space and is put with only half of the usual operator separation into the circuit (for this reason, it can be put at the beginning of a wire without creating weird shifts with respect to the “unslashed” registers—it is put in the initial line that every wire even without an operation has). Hence, you should normally only use the `slash` gate as the very first gate in a circuit. To get the vertical stopper mark, we abuse a `barrier` on just a single wire and turn it from dashed to solid before `discarding`.



### test17 (example from Nielsen paper on cluster states)

Updated in 0.1.1



```
\begin{tikzpicture}
\begin{yquant}
  qubit {\ket{q_0}} = \ket{\psi} q;
  qubit {\ket{q_{\idx}}} = \ket{+} q[+2];
  qubit {\ket{q_3}} = \ket{\phi} q[+1];


  zz q[(0-1), (2-3)];
  zz (q[1-2]);
  dmeter {\H$} q[1-2];
\end{yquant}
\end{tikzpicture}
```

This example shows how the multi-qubit delimiter (the parenthesis) can even be used within indices.



### test18 (multiple-control bullet op)

Updated in 0.1.2



```
\begin{tikzpicture}
\begin{yquant}
  qubit {\ket{q_{\idx}}} =
    \ket{\Ifcase\idx\relax \psi \Or + \Or +
    \Or \phi \Fi} q[4];

  zz (q);
  dmeter {\H$} q[1, 2];
\end{yquant}
\end{tikzpicture}
```


This gate is probably a generalization of  $zz, \mathbb{1} - 2|1 \dots 1\rangle\langle 1 \dots 1|$ , and indeed since version 0.1.2, we can use `zz` for this purpose. This time, we used the case distinction method in the initialization, as already alluded to before.



## 6.2 qcircuit documentation

For a better orientation, we use the same section headings as the `qcircuit` manual. The manual uses unnamed registers a lot; often, we will use the `yquant*` environment to make things more concise. As the `qcircuit` manual uses a bit larger separation between the operators than `yquant`'s default, we globally say `\yquantset{operator/separation=1em}`.


### 6.2.1 I. Introduction



Updated in 0.5, 0.4,  
0.1.1

```
% \useyquantlanguage{groups}
\begin{yquantgroup}
  \registers{
    qubit {} q[3];
  }
  \circuit{
    box {$U$} q[2] | q[0, 1];
  }
  \equals
  \circuit{
    box {$V$} q[2] | q[1];
    cnot q[1] | q[0];
    box {$V^\dagger$} q[2] | q[1];
    cnot q[1] | q[0];
    box {$V$} q[2] | q[0];
  }
\end{yquantgroup}
```

The best way to realize circuit equalities is with the help of `groups` language extension, which is documented in section 7.1.



Updated in 0.4

```

\begin{tikzpicture}
  \begin{yquant}
    qubit {\ket{\psi}} a;
    qubit {\ket{0}} b[2];


    h b[1];
    cnot b[0] | b[1];
    cnot b[0] | a;
    h a;
    align a, b;
    measure a;
    [direct control]
    measure b[0];

    x b[1] | b[0];
    z b[1] | a;

    discard a;
    discard b[0];
    output {\ket{\psi}} b[1];
  \end{yquant}
\end{tikzpicture}

```

Here, we see how to use a measurement as a direct output for the next controlled operation.



Updated in 0.4

```

% \usetikzlibrary{quotes}
\begin{tikzpicture}
  \begin{yquant}
    qubit {} msg[3];
    nobit syndrome[3];

    [this subcircuit box style={dashed, "Syndrome Measurement"}]
    subcircuit {
      qubit {} msg[3];
      [out]
      qubit {\ket{0}} syndrome[3];

      cnot syndrome[0] | msg[0];
      cnot syndrome[0] | msg[1];
      cnot syndrome[1] | msg[1];
      cnot syndrome[1] | msg[2];
      cnot syndrome[2] | msg[0];
      cnot syndrome[2] | msg[2];

      dmeter {\mathcal{M}_{\text{a+idx}}} syndrome;
    } (msg[-2], syndrome[-2]);

    ["Recovery"]
    box {\mathcal{R}} (msg) | syndrome;
    discard syndrome;
  \end{yquant}
\end{tikzpicture}

```

The example demonstrates how to put a description next to a gate. In general, those descriptions should be realized using the `TikZ` feature `label`. Using the `TikZ` library `quotes`, the label is most easily specified. Since the label is not part of the valid arguments and also cannot be found in the `/yquant` path, it is automatically passed to `/yquant/operator style`.


To enclose a part of the circuit by a rectangle, we use a subcircuit. We define the incoming `qubits` in the outer circuit, they will have the default attribute `[inout]`; the syndrome registers, which are created only in the subcircuit enter as `nobits` and consequently have the `[out]` attribute. It is important to note that both the dashed style as well as the `label` (here with quoted syntax) are specified only inside `/yquant/this subcircuit box style`. This ensures that they are not also attached to every single gate in the subcircuit.

Then we see how to apply an operation to multiple registers in parallel while using the `\idx` macro to still give them a different text. Since `\idx` gives a numerical index (zero-based), we exploit the ASCII code (actually, this document

is compiled in Unicode mode...) to turn this into a letter.

Note that it could have become necessary to pass the `overlay` attribute to the recovery gate, as it is a multi-register gate with a `label`, meaning that `yquant` cannot reliably distribute its total vertical extent over its constituent registers. However, as the  $\mathcal{R}$  together with the label in total were not higher than the three-qubit gate would have been anyway, this was not necessary here. In general, don't use `overlay` unless necessary; maybe a future version will even be able to handle the more difficult cases better.

Finally, we will give a similar circuit by using the `TikZ` interface instead of subcircuits, this time also showing how we can change the shape of the measurement gate to one as in the `qcircuit` manual:



```

% \usetikzlibrary{fit, quotes}
\begin{tikzpicture}
  \begin{yquant}
    qubit {} msg[3];
    [name=init]
    qubit {\ket{0}} syndrome[3];

    [name=scnot0]
    cnot syndrome[0] | msg[0];
    cnot syndrome[0] | msg[1];
    cnot syndrome[1] | msg[1];
    cnot syndrome[1] | msg[2];
    cnot syndrome[2] | msg[0];
    cnot syndrome[2] | msg[2];
    [name=smeas, shape=yquant-rectangle, rounded corners=.45em]
    dmeter {\mathcal{M}_{\text{a+}}\text{ syndrome}} syndrome;
    ["Recovery"]
    box {\mathcal{R}} (msg) | syndrome;
    discard syndrome;
  \end{yquant}
  \node[draw, dashed, fit=(init-p0) (scnot0-p0) (smeas-2), "Syndrome
    ↳ Measurement"] {};
\end{tikzpicture}

```

We name several elements that visually form the enclosing rectangle; then, we use the **TikZ** library `fit` to put a node around them all. Any gate can be given a custom shape; here, we use a `yquant-rectangle`, which is the analogue to **TikZ**'s rectangle and thus supports the standard rounded corners style.

### 6.2.2 IV. Simple Quantum Circuits




```


\begin{tikzpicture}
  \begin{yquant*}
    x q;
  \end{yquant*}
\end{tikzpicture}

```

## A. Wires and gates



```
\begin{tikzpicture}
\begin{yquant*}
h a;
align a, b;
z a;
x b;
h a;
\end{yquant*}
\end{tikzpicture}
```



```
\begin{tikzpicture}
\begin{yquant*}
box {$U$} a;
box {$U^\dagger$} b;
setstyle {->} -;
\end{yquant*}
\end{tikzpicture}
```


`yquant` allows to change wire styles by means of the `setstyle` and `addstyle` pseudo-gates. Here, we use the gate on all wires in order to set an arrow style. Note that arrowheads are actually very special in two respects:

- `yquant` draws continuous wires for as long as possible. In this example, the wire path extends from the very left to the end of the circuit; `yquant` does not draw a wire *to* the gate and then a separate one *from* the gate to the next or the end. The only way to force `yquant` to draw multiple wires is to change the wire style or type mid-circuit. For example, by saying `addstyle {} -;`, all wire paths will be separated at the current position, which *in theory* allows to draw arrowheads on intermediate wires.
- *In practice*, this will not work due to the clipping commands that `yquant` installs. Every wire extends from the center of the left to the center of the right gate, and the gate's shape acts as a clipping path. Consequently, though the arrowhead is drawn, it is actually drawn at the center of the gate instead of the west anchor and then clipped away (unless the gate is small, in which case you might still see some fragments of the arrowhead).


Changed in 0.1.2  
Updated in 0.1.2

Thus, it is currently not possible to use arrowheads on intermediate wires. If you really need to do this (say, for only a single gate), you may experiment with the `TikZ` shorten keys, which allow you to manually reduce the length of the wire, but the amount of reduction must be hand-computed for every gate. If you need this more often, consider filing a feature request.

## B. CNOT and other controlled single qubits gates




```
\begin{tikzpicture}
  \begin{yquant*}
    cnot a[1] | a[0];
    cnot a[0] | a[1];
  \end{yquant*}
\end{tikzpicture}
```



```
\begin{tikzpicture}
  \begin{yquant*}
    cnot q[2] | q[0];
    cnot q[0] | q[1-3];
    box {$U$} q[0] | q[2];
  \end{yquant*}
\end{tikzpicture}
```

Updated in 0.1.1

## C. Vertical wires




```
\begin{tikzpicture}
  \begin{yquant*}
    box {$U_{\The\numexpr\idx+1}$} q[0, 2] | q[1];
  \end{yquant*}
\end{tikzpicture}
```

Updated in 0.4,  
0.1.1


There is no direct support for this construction, but as with the initialization of a vector registers, `yquant` allows to access the macro `\idx` within an operator value. This macro follows the same rules as the name suffix, i.e., it assigns indices (zero-based) to the target registers in top-to-bottom order, regardless of which order was specified in the target list. Since we instead want a one-based subscript, we need to add one. Note that if you want to output `\idx` directly or within an unexpandable expression, you don't need to take any

action. However, here, `\the` is expandable; and since `yquant` needs to process all its output twice (first in order to determine the vertical spacing, second to actually typeset), you must manually take care that the command is *not* expanded prematurely by saying `\protect\the` instead, for which `yquant`, with a `compat` setting of at least 0.4, provides the shorthand `\The`. Had we used the plain  $\TeX$  `\the` instead, the subscript would have been “1” for both operators.

#### D. Labeling input and output states



```
\begin{tikzpicture}
  \begin{yquant*}
    qubit {\ket{1}} q[2];
    cnot q[0] | q[1];
    output {\ket{idx}} q;
  \end{yquant*}
\end{tikzpicture}
```



```
% \usetikzlibrary{calc}
\begin{tikzpicture}
  \begin{yquant*}
    {
      \yquantset{every multi label/.style={every
        \hookrightarrow node/.style={anchor=east, midway}}}
      init {\ket{0^k}} (a[-1]);
    }
    init {\ket{psi}} (b[-1]);
    [name=cinit]
    qubit {\Ifcase\idx\relax A$\Or$B$\Fi} c[2];
    \node[anchor=east] at
      \hookrightarrow ($ (cinit-0.west)!.5!(cinit-1.west)$) {\ket{psi}};
  \end{yquant*}
\end{tikzpicture}
```

Updated in 0.4,  
0.1.1

Here, three different styles for the initialization of multi-qubit labels are used. The second one (using a curly brace) corresponds to the default. It is overwritten for the first qubit, and to make this modification local, this is done in a group. The third qubit pair uses an overall label and additionally individual labels on the lines. The recommended way to do this starting from version 0.4 is to add the “special” label by means of a `TikZ` command.




## 6.2.3 V. More Complicated Circuits: Multiple Qubit gates and Beyond

### A. Multiple qubit gates



```
\begin{tikzpicture}
  \begin{yquant*}
    box {$U^\dagger$} (a[-2]);
  \end{yquant*}
\end{tikzpicture}
```

Updated in 0.1.1




```
\yquantdefinebox{dots}[inner sep=0pt]{$\dots$}
\begin{tikzpicture}
  \begin{yquant}
    qubit {} a;
    cbit {} b;
    [register/minimum height=0pt, register/minimum
     ↪ depth=0pt]
    nobit ellipsis;
    qubit {} c;

    dots ellipsis;
    box {$U$} (a, b, ellipsis, c);
    dots ellipsis;
  \end{yquant}
\end{tikzpicture}
```

Updated in 0.4,  
0.1.1

This demonstrates how a register of type `nobit` might even be useful if the register is never used and no subcircuits are involved. Note how we overwrite the default minimum height and depth setting for this register only. Additionally, we for the first time define our own gate, which we call `dots`. As we define our own style, it does not inherit from `/yquant/operators/every box`; hence, we only need to overwrite the `inner sep` coming from `TikZ`'s defaults.




```
\begin{tikzpicture}
  \begin{yquant*}
    box {\symcal F} (a[-1]);
    box {\symcal G} (a[0, 2]);
  \end{yquant*}
\end{tikzpicture}
```

This demonstrates `yquant`'s capabilities of discontinuous multi-qubit gates. `yquant` automatically splits multi-qubit gates into slices of directly adjacent wires (which, for the  $\mathcal{G}$  case, are the single wires  $a[0]$  and as second slice  $a[2]$ ).


Updated in 0.1.2,  
0.1.1

## B. Measurements and classical bits



```
\begin{tikzpicture}
  \begin{yquant*}
    measure a;
    dmeter {\chi} b;
    measure {\ket{\xi_{\pm}}} c;
  \end{yquant*}
\end{tikzpicture}
```


The “tab” and “measure” type are not supported yet. Extracting a meter symbol on its own will not be supported. If you are interested in the code, have a look at `yquant-shapes.tex` and search for the `yquant-measure` shape.



```
\begin{tikzpicture}
  \begin{yquant*}
    [shape=yquant-rectangle, rounded corners=.45em,
     \direct control]
    measure {Codebit} a;
    box {\chi} b | a;
    discard a;
    measure b;
  \end{yquant*}
\end{tikzpicture}
```

Rectangles with rounded corners are not a specific style, but since the `yquant-rectangle` shape internally uses `\pgfpathrectangle`, the ordinary `TikZ` option can be used (also, an inset specification can control how much the corner is rounded).

Updated in 0.4,  
0.1.2




```
\begin{tikzpicture}
\begin{yquant}
qubit {\ket{\psi}} q;

measure {\ket{\xi_{\pm}}} q;
\end{yquant}
\end{tikzpicture}
```



```
\begin{tikzpicture}
\begin{yquant*}
dmeter {Bell} (a[0, 1]);
discard a;
\end{yquant*}
\end{tikzpicture}
```


Updated in 0.1.1



```
\begin{tikzpicture}
\begin{yquant*}
measure {\ket{\xi_{\mp}}} (a[-1, 3]);
\end{yquant*}
\end{tikzpicture}
```

Updated in 0.1.2,  
0.1.1

Multi-qubit gates (including measurements) on non-adjacent registers are properly supported. As explained in section 2.4, there is one main and multiple subordinate gate in such a discontinuous multi-qubit operation (though at the moment, the `measure` gates with text is the only gate that makes this distinction). In our case, the main part contains the measurement symbol and the text, while the subordinate gates only contain the text. By default, `yquant` uses the first slice as main part, but you may influence this by preceding what you want to be “main” by a star:




```
\begin{tikzpicture}
\begin{yquant*}
measure {\ket{\xi_{\mp}}} (a[-1, *3]);
\end{yquant*}
\end{tikzpicture}
```

### C. Non-gate inserts, forcing space, and swap

Updated in 0.1.1




Defective Circuit



```
\begin{tikzpicture}
  \begin{yquant*}
    [name=sw]
    swap (a[0-1]);
    [draw=none]
    box {$X$} a[1];
    slash b;
    box {$H^{\otimes n}$} b;
    \node[anchor=199] at (sw-0.north) {Defective
      \(\rightarrow\) Circuit};
  \end{yquant*}
\end{tikzpicture}
```

Here, the intermediate text was inserted by using a `box` without drawing. Another way would be to use an `init` command, although this is semantically wrong (probably).




```
\begin{tikzpicture}
  \begin{yquant*}
    qubit {} a;
    [name=ypos]
    qubit {} b[3];

    cnot a | b[0];
    [name=left]
    cnot a | b[1];
    hspace {7mm} -;
    [name=right]
    cnot a | b[2];
  \end{yquant*}
  \path (left |- ypos-0) -- (right |- ypos-1)
    \(\rightarrow\) node[midway] {$\dots$};
\end{tikzpicture}
```

Note how the register range `-` was used to denote all registers. We positioned the dots by first naming the relevant registers, so that the vertical position is at the coordinates `ypos-0` and `ypos-1`; and then, we also named the `cnot` gates, so that we are able to discern the horizontal position.

## D. Barriers




```
\begin{tikzpicture}
  \begin{yquant*}
    x a[0, 1];
    barrier (a);
  \end{yquant*}
\end{tikzpicture}
```

Updated in 0.1.1

Now the `qcircuit` manual lists three circuits with barriers at different positions. They cannot be drawn with `yquant`; however, since neither of them is a valid circuit (no indication whether the control is positive or negative), this is of no concern.

## E. How to control anything



```
\begin{tikzpicture}
  \begin{yquant*}
    zz (a[0, 2]);
    cnot a[1] ~ a[0];
    zz (a[2, 3]);
    h a[3] | a[0] ~ a[1];
    measure a[2, 3];
    box {$U$} (a[0, 1]) | a[3] ~ a[2];
    discard a[2, 3];
  \end{yquant*}
\end{tikzpicture}
```


Updated in 0.1.1

Note that it is not possible to draw a control to measurement (the measurement operations are explicitly defined not to accept controls): Either the measurement is performed or not (which transforms the register type), but a measurement conditioned on a quantum state is not possible. In principle, one could think of a measurement conditioned on a classical register (in which case the register type cannot change, as maybe the state stays quantum; the measurement operation then is similar to a complete dephasing). If there is need for this, please file a feature request. But note the relatively common (though unsupported by `yquant` at the moment) use of control lines that directly go from the measurement operator to the controlled operation; in this case, the opposite direction would be meant by using the same notation.

## 6.2.4 VI. Bells and Whistles: Tweaking Your Diagram to Perfection

For options how to configure the circuits, refer to section 3.


### A. Spacing



```
\begin{tikzpicture}
  \begin{yquant*}
    swap (a[0, 1]);
    box {$T^\dagger$} a[2] | a[1];
    swap (a[0, 1]);
  \end{yquant*}
\end{tikzpicture}
```

Updated in 0.1.1

### B. Labeling



```
\begin{tikzpicture}
  \begin{yquant}[every initial
    ⇨ label/.style={anchor=south east, yshift=1mm},
    ⇨ every post measurement control=direct,
    ⇨ operators/every box/.append style={draw=none}]
    qubit {\rlap{\hspace{2mm} $a$}} a;
    qubit {\rlap{\hspace{2mm} $b$}} b;
    nobit out;
    hspace {5mm} -;


    measure b;
    box {$B$} out | b;
    measure a;
    box {$A$} out | a;
    discard -;
  \end{yquant}
\end{tikzpicture}
```

Updated in 0.4

We support measurements with vertical outputs, but only if they replace the positive control of some action. Here, we fake this behavior by introducing an invisible register at the bottom, which will contain the outputs. In order to disable the line around the `boxes`, we used the `/yquant/operators/every box` style, which here was most convenient, as the only `boxes` in use are those without an outline. However, if we instead want to say `[draw=none]` as an attribute to the `boxes`, this will also remove the outline of the measurements. The reason for this is that giving this as an attribute will in fact populate

`/yquant/operator style`; and internally, the measurement will be nested within the same scope that draws the `box`—so the options given to the `box` will be inherited by the `measurement`. As an operator style overwrites default styles, this will also apply to the measurements. Hence, to circumvent this, we would have to additionally say `[draw]` as an attribute to the `measurements`, although this is already included in their native style. Repositioning the initial labels needs some care and manual fine-tuning.

### C. Grouping



Updated in 0.4,  
0.1.1

```
% \usetikzlibrary{fit}
\begin{tikzpicture}
  \begin{yquant*}[register/separation=3mm]
    cnot a[2] | a[0];
    cnot a[2] | a[1];
    [name=left]
    h a[0, 1];
    z a[2];
    cnot a[1] | a[0];
    [name=righttop]
    h a[0];
    [name=rightbot]
    h a[1] | a[2];


    hspace {2mm} -;
  \end{yquant*}
  \node[draw, dashed, fit=(left-0) (left-1) (righttop) (rightbot-0)] {};
\end{tikzpicture}
```

Note that `\begin{yquant*}` must not be followed by a line break (unless masked by `%`) if options follow. Also note that here, we cannot make use of a subcircuit due to the very last control, which would then control an inner gate of said subcircuit—but they are not exposed.

## 6.3 quantikz documentation

Again, our section headings will be the same as in the `quantikz` manual. And since `quantikz` also has even more space between the gates, we globally say `\yquantset{operator/separation=4mm}`.

### 6.3.1 II. A single wire



```
\begin{tikzpicture}[label position=north east, every label/.style={inner
↪ sep=1pt}]
\begin{yquant}
  qubit {\ket{0}} a;


  phase {\alpha} a;
  h a;
  phase {\beta} a;
  h a;
  phase {\gamma} a;

  [every output/.append style={align=center}]
  output {Arbitrary\\pure state} a;
\end{yquant}
\end{tikzpicture}
```

The captions of `phase` commands are internally implemented using `TikZ` labels. At the moment, it is not possible to change any label options on a gate-type basis, only locally or fully globally (`TikZ` feature request #811).



## A. Measurements




```
% \usetikzlibrary{quotes}
\begin{tikzpicture}
  \begin{yquant*}
    ["$0$"]
    measure a;
    discard a;

    init {} a;
    dmeter {"$1$"} a;
    discard a;
  \end{yquant*}
\end{tikzpicture}
```

Other measurement shapes are not supported at the moment.

## B. Wires and arrows



Updated in 0.1.2

```
% \usetikzlibrary{quotes}
\begin{tikzpicture}
  \begin{yquant}[operator/separation=1cm, every label/.append
    ↪ style={align=center}]
    qubit {"$ket0$\\initial state"} a;

    [draw=none]
    box {"$X$"} a;

    ["$0$/$1$", type=qubit]
    measure a;


    addstyle {->} a;
    output {"$ket1$"} a;
    \yquantset{operator/separation=5mm}
  \end{yquant}
\end{tikzpicture}
```

This example demonstrates how to instruct the `measure` gate to use a different output type than the standard `cbit`.

In general, any macros that are used within a `TikZ` path or a `yquant` operation must not be fragile, or must be preceded with `\protect`. In this example, `\\`

is a robust command (at least in newer kernels), so protection is not required. Since it may occur quite frequently that `yquant` is used within a center environment or in `\centering` mode (in which `\` is still fragile), `yquant` takes care of this (it actually robustifies `\@centercr`, which is the meaning of `\` in these surroundings—and which is now incorporated into the  $\TeX$  kernel as of June 2021).


In order to change the style of an individual wire, we use `addstyle`. To make the final line shorter, we change the operator separation by issuing `\yquantset` at the end.



```
\begin{tikzpicture}
\begin{yquant}
qubit {\ket{0}} q;
[name=h]
h q;
discard q;
\path[/yquant/every wire, /yquant/every qubit
  \> wire, -Stealth] (h) --| ++(1cm, -.5cm)
  \> node[below] {trash};
\end{yquant}
\end{tikzpicture}
```

New in 0.4

Here, we use an ordinary `\path` command to reproduce the “trash” line. This time, we chose to use the appropriate styles as `yquant` itself would do it instead of just saying `\draw` without the options, which would also have worked.



```
% \usetikzlibrary{quotes}
\begin{tikzpicture}
\begin{yquant*}
qubit {\ket{0}^{\otimes n}} a;
["north east:3" {font=\protect\footnotesize,
  \> inner sep=0pt}]
slash a;
h a;
\end{yquant*}
\end{tikzpicture}
```

Updated in 0.4


Again, you see an example of how some commands need to be `\protected` when used in `yquant` options, and that you can indeed exploit all features of the quotes library.



$$|0\rangle^{\otimes n} \Rightarrow \boxed{H}$$

```
\begin{tikzpicture}
  \begin{yquant}
    qubits { $\ket{0}^{\otimes n}$ } a;
    h a;
  \end{yquant}
\end{tikzpicture}
```

### 6.3.2 III. Multiple Qubits




```
\begin{tikzpicture}
  \begin{yquant}
    qubit { $\ket{0}$ } a;
    qubit { $\ket{0}$ } b;

    h a, b;
    cnot b | a;
    box { $U$ } a ~ b;
    zz (a, b);

    [after=a]
    qubit {} c;

    swap (a, c);
    box { $U$ } c | a ~ b;
  \end{yquant}
\end{tikzpicture}
```


This example demonstrates the use of the `after` argument that instructs the register creation to begin the register only after the current position of another register that already exists. Note that this argument will always make the wire begin *at the right end* of the last gate of the referenced register; however, if—as is the case here—this gate is shorter than `/yquant/operator/minimum width`, this might not coincide with the visual right end.



Updated in 0.4,  
0.1.2, 0.1.1

```
\begin{tikzpicture}
  \begin{yquant*}
    [name=c]
    cnot a[0, 2] | a[1];
    [name=m, direct control]
    measure a[1];
    discard a[2];
    box {$U$} a[0] | a[1];
    \path[/yquant/every wire, /yquant/every qubit wire] (c-1) --
      \quad (m.center |- c-1);
    discard a[1];
  \end{yquant*}
\end{tikzpicture}
```

Here, we manually extended the wire on the last register. We could instead have performed an `align` gate before the discarding process, then, the wire line would have been extended by `yquant`; but since `align` aligns at the *right end* as opposed to the center of the gate, the wire line would have been a bit longer. Still, this `TikZ` wire is inferior to a wire drawn by `yquant`, as it does not use clippings: the connection with the `cnot` gate may not be accurate; in particular, if the wire is of a different color or if you need to draw classical or bundle wires, the connection will become unpleasant.




```
\begin{tikzpicture}
  \begin{yquant*}
    cnot a[1, 2] | a[0];
    measure a[1], a[2];
    box {$U$} a[0] | a[1];
    box {$V$} a[0] | a[2];
    discard a[1]-;
  \end{yquant*}
\end{tikzpicture}
```

Updated in 0.1.1

`yquant` doesn't offer anything comparable to the new `\ctrlbundle` command; and as the bundle lines are spaced much more tightly in `yquant`, this would not really make sense.

### 6.3.3 IV. Operating on many Qubits




```
\begin{tikzpicture}
\begin{yquant*}
init {\ket{0}^{\otimes 3}} (a[-2]);

box {\$U\$} (a[1-2]) | a[0];
measure a[0];
discard a[0];
output {\ket{11}} (a[1-2]);
\end{yquant*}
\end{tikzpicture}
```

Updated in 0.1.1


Multi-qubits inputs are possible using the `init` command. The text assigned to a register declaration is always for an individual register.



```
\begin{tikzpicture}
\begin{yquant*}[register/minimum
↪ height=6mm, register/minimum
↪ depth=6mm]
hspace {7.5mm} a;
h a;
hspace {7.5mm} a;
[x radius=1cm]
box {\$U\$} (b, c);
cnot b | a;
measure a;
discard a;
\end{yquant*}
\end{tikzpicture}
```

Updated in 0.4

`yquant` does not use a grid layout: operators are stacked next to each other. Therefore, there is no automatic centering of a column, though it could be emulated using hand-crafted `hspace` commands, as was done here (the Hadamard gate uses the `/yquant/operator/minimum width`, which is 5mm, while the large box has a width of 2cm, so that we need two 7.5mm spacings at the end, as the `hspace` pseudo-gate only inserts exactly the space you give, but not additional [twice] `/yquant/operator/separation`, as would be the case for a hypothetical zero-width gate). In fact, we don't even need the second `hspace`, since the two-qubit `cnot` will automatically enforce correct alignment.



Updated in 0.4

```
\begin{tikzpicture}
\begin{yquant}[register/separation=3mm, every nobit output/.style={}]
qubit {} a[4];
[every inspect/.append style={outer xsep=0pt}, operator/minimum
↪ width=0pt, font=\footnotesize, name=sub]
subcircuit {
\yquantset{operator/separation=0pt}
qubit {} x[2];
qubit {} y;
discard -;

inspect {$x$} (x);
[inner xsep=0pt]
inspect {$y\phantom{f}$} y;

[shape=yquant-init, decoration={mirror}]
inspect {\hspace{4mm} $x$} (x);
[shape=yquant-init, inner xsep=0pt]
inspect {$y \oplus f(x)$} y;
} (a[1-3]) | a[0];
\node at (sub) {$U$};
settype {qubit} a;
\end{yquant}
\end{tikzpicture}
```

We use quite some tricks to achieve such a layout. We use a subcircuit as a container and `inspect` gates to indicate the inputs and output states accurately. As those are ordinary gates, we reset `/yquant/operator/minimum width`, so that the “*y*” indication is not too long. Additionally, they are usually meant to be used within a circuit, i.e., they have an additional margin denoted by the `outer xsep`, which we also remove. Then, within the subcircuit, we reset the `/yquant/operator/separation`, which would insert additional whitespace at the beginning. It is important to do this within the subcircuit and not as an attribute; else, we would also remove the outer lines going into the subcircuit. Initial or final `inspect` gates without a brace do not really need the separation between brace tip and text (`inner xsep`), so we also remove it. The output gates should have their braces and separations at the other side, which cor-

responds to changing their shape from `yquant-output` to `yquant-init` and mirroring the decoration (as in `/yquant/every label`). To get the desired right-alignment, we hand-tailor an `\hskip` that enlarges the upper output label—automatic alignments would not work here: putting the two `inspects` together with a case distinction on `\idx` would center them; using `outputs` would left-align them.


Finally, we have to deal with the caption of the gate, which should be absolutely centered with respect to the subcircuit and not have any influence on the spacing—so we just insert it retrospectively as an ordinary `TikZ` node.

Also note the use of `discard` and `settype` since we needed wires before and after the subcircuit, which must match the inner wires in type, but we actually do not want to have inner wires.



```
\begin{tikzpicture}
\begin{yquant*}
  box {\sqrt{Z}} a;
  box {X} b;
  box {\sqrt{\mathrm{SWAP}}} (a, b);
  measure a;
\end{yquant*}
\end{tikzpicture}
```

This time, we did not artificially discard the lines.




```
\begin{tikzpicture}
\begin{yquant}
  qubit {c_{\idx}} c[4];
  box {M\A\J} (c[-2]);
  box {M\A\J} (c[1-]);
\end{yquant}
\end{tikzpicture}
```

Notice here that the vertical spacing is uneven. `yquant` realizes that the minimal vertical spacing will not be enough to account for the multi-qubit boxes. However, when it tries to adjust positions accordingly so that the last gate fits, this will of course not change anything for the first wire, which is not contained in the gate. After having increased the spacing, `yquant` realizes that this already was enough to accommodate for the first gate, so no further action is taken. In order to get a more even spacing, just increase `/yquant/register/minimum height` and `/yquant/register/minimum depth`.

Updated in 0.4,  
0.1.1


## A. Different connections



```
\begin{tikzpicture}
  \begin{yquant}[register/default name=]
    qubit a;
    cbit b;
    nobit c;
    cbit d;
    qubit e;
    box {$U$} (-);
    settype {qubit} c;
  \end{yquant}
\end{tikzpicture}
```

This example demonstrates the declaration of a non-existing register and the `settype` pseudo-gate that acts as a zero-width, no-content `init` gate.


## 6.3.4 V. Slicing




```
\begin{tikzpicture}
  \begin{yquant}
    qubit {} a[3];
    h a[0];
    [red, thick, label=step]
    barrier (a);
    cnot a[1] | a[0];
    measure a[0];
    discard a[0];
    cnot a[2] | a[1];
    h a[1];
  \end{yquant}
\end{tikzpicture}
```

There is nothing like a `slice` all keyword, as `yquant`'s underlying layout is not grid-based. Changing the style of slice captions simply means providing label options. This time, we used the `label` key instead of the shorter syntax provided by the `quotes` library, which is of course also possible.





```
% \usetikzlibrary{quotes}
\begin{tikzpicture}[every label/.style={rotate=40, anchor=south west}]
\begin{yquant}[operators/every barrier/.append style={blue, thick}]
  qubit {} a[3];
  h a[0];
  ["slice 1"]
  barrier (-);
  cnot a[1] | a[0];
  ["slice 2"]
  barrier (-);
  measure a[0];
  discard a[0];
  cnot a[2] | a[1];
  ["slice 3"]
  barrier (-);
  h a[1];
\end{yquant}
\end{tikzpicture}
```



Updated in 0.4

```

% \usetikzlibrary{quotes}
\begin{tikzpicture}[label distance=4mm]
  \begin{yquant}[operators/every barrier/.append style={red, thick,
    ↪ shorten <= -4mm, shorten >= -4mm}]
    qubit  $\ket{0}$  a;
    h a;
    ["1"]
    barrier a;
    phase  $\varphi$  a;
    ["2"]
    barrier a;
    h a;
    ["3"]
    barrier a;
    output  $\cos\frac{\varphi}{2} \ket{0} - i\sin\frac{\varphi}{2} \ket{1}$  a;
  \end{yquant}
\end{tikzpicture}

```

Usually, the `shorten` keys do not have any effect on `yquant` operations, since the latter are all made up of nodes. However, the `yquant-line` shape explicitly takes care of correctly handling them. It is the only one that does so. Since barriers usually end quite closely to the wires—and the default dashed style may make this worse—the shortening may often prove useful. Note that if the barriers are enlarged by means of negative shortenings, this will not affect the bounding box and you must take care of appropriately shifting labels. The internal register height calculations might be inconsistent for multi-register barriers with shortening: While `yquant` takes care of enlarging the registers so that there is enough space for placing the `barrier` with its *original* (single-register) height, its actual height of the registers is only known at the second stage in calculation; but applying shortenings after this stage would require another iteration of height calculation. Hence, multi-register barriers that are enlarged by a lot will probably look bad unless you add manual spacing to the appropriate registers. Also note that we used much larger magnitudes in order to achieve a similar appearance as in `quantikz`. To avoid that the large distance also affects the `phase` gate badly, we locally reset the distance; for this, there are two ways. The easiest one is to make use of the fact that the value of the `phase` gate is passed directly as `label` argument, so that we can locally reset the distance. The other possibility would be to write

```

{
  \yquantset{/tikz/label distance=0pt}
  phase {$\varphi$} a;
}


```

since due to the aforementioned lack of support for a style that sets the options in **TikZ**, we must manually use a (grouped) **\yquantset** instruction for this. Note that whenever you change a **TikZ** style in a **yquant** environment, use the **\yquantset** macro, *not* **\tikzset** or **\pgfkeys**. Not only will the latter two not automatically restart the parser (so that you would have to issue **\yquant** after their use), but **yquant** has to process all its content twice in order to properly determine the register height. Only **\yquantset** will be properly captured and re-issued at the correct position when the content is actually typeset. Had we written **\tikzset{label distance=0pt} \yquant**, no effect at all would have been visible, since this command would only have taken effect in the first (invisible) round when **yquant** determines heights.

**yquant** does not provide a mechanism for vertical labels, but you may of course just insert line breaks at appropriate positions (and set the **align** property of the labels).

### 6.3.5 VI. Spacing

#### A. Local adjustment



```

\begin{tikzpicture}
  \begin{yquant}[register/default name=]
    [register/minimum depth=2cm]
    qubit a;
    qubit b;
    qubit c;

    h a;
    x b-;
    hspace {2cm} -;
    x a;
    z b-;
    h a;
    z b-;
  \end{yquant}
\end{tikzpicture}

```

Updated in 0.4


The vertical distance between registers is calculated by `yquant` automatically based on the height and depth that `yquant` find for this particular register—i.e., how much space is required above and below the wire line for all the gates. In order to enlarge these values, reset `/yquant/register/minimum height` or `/yquant/register/minimum depth` to a different value. It is not possible to artificially *reduce* the calculated heights and depths, as this would result in overlapping gates. However, sometimes it might be required to exclude a certain gate from the calculation; then, use the `overlay` attribute.




```
\begin{tikzpicture}
  \begin{yquant*}
    [x radius=1cm]
    x a;
    box {\hbox to 1cm{\hfil$X$\hfil}} a;
    hspace {1cm} a;
    x a;
    discard a;
  \end{yquant*}
\end{tikzpicture}
```

Here, we demonstrate two possibilities to enlarge a box: The first is by specifying its size in terms of the `x radius` or `y radius` keys beforehand. Those values serve as minimum sizes and would be extended if the text extended beyond the box. The second option is to just enlarge the text artificially by explicitly putting it into a fixed-width box. Note that in the first case, the *radius* is specified, i.e., the half-width, while in the second case, it is the *total* width (both times modulo the inner separation). Also note that the `/yquant/operator/minimum width` style is unsuitable for the given task: it would not change the visual width, only what `yquant` assumes its width to be.

## B. Global Adjustment



```
\begin{tikzpicture}
  \begin{yquant*}[operator/separation=1cm]
    h a;
    phase {\beta} a;
    h a;
  \end{yquant*}
\end{tikzpicture}
```



```
\begin{tikzpicture}
  \begin{yquant*}[register/minimum height=0pt,
    ↪ register/minimum depth=0pt]
    x a[0, 2];
    zz (a[0, 1]);
    x a[0];
    h b;
  \end{yquant*}
\end{tikzpicture}
```


By default, `yquant` will use the height and depth that is required by the individual gates, but at least `/yquant/register/minimum height` or, respectively, `/yquant/register/minimum depth` (which default to 1.5mm). Only manually reducing the default height will produce the cramped spacing displayed here.

Updated in 0.4,  
0.1.1

## C. Alignment




Updated in 0.5, 0.4



```
\begin{tikzpicture}
  \begin{yquant*}
    x a[0];
    cnot a[1] | a[0];
  \end{yquant*}
\end{tikzpicture}
$=$
\begin{tikzpicture}
  \begin{yquant*}
    cnot a[1] | a[0];
    x a;
  \end{yquant*}
\end{tikzpicture}
```

Not specifying anything for the vertical alignment will lead to the common **TikZ** problem: the baseline will be at the bottom, which is particularly bad in this case due to the missing  $X$  gate. The keys for minimal register sizes do not help here, since they only affect **yquant**'s internal handling, but not the bounding box calculated by **TikZ**. The recommended way to draw circuit equations is always with the **groups** language extension.



```
% \useyquantlanguage{groups}
\begin{yquantgroup}
  \registers{
    qubit {} q[2];
  }
  \circuit{
    x q[0];
    cnot q[1] | q[0];
  }
  \equals
  \circuit{
    cnot q[1] | q[0];
    x q;
  }
\end{yquantgroup}
```



$$\left\{ \begin{array}{c} |x\rangle \text{---} [H] \text{---} \bullet \\ |y\rangle \text{---} \oplus \end{array} \right\} \mapsto |\psi_{x,y}\rangle \mapsto \left\{ \begin{array}{c} \bullet \text{---} [H] \text{---} |x\rangle \\ \oplus \text{---} |y\rangle \end{array} \right\}$$

Updated in 0.5  
New in 0.4

```
% \usequantlanguage{groups}
\begin{yquantgroup}
  \registers{
    qubit {} q[2];
  }
  \circuit{
    init {\ket x$} q[0];
    init {\ket y$} q[1];

    h q[0];
    cnot q[1] | q[0];
    output {} (-);
  }
  \equals[{\mapsto\quad\ket{\psi_{x, y}}\quad\mapsto}]
  \circuit{
    init {} (q);
    cnot q[1] | q[0];
    h q[0];

    output {\ket x$} q[0];
    output {\ket y$} q[1];
  }
\end{yquantgroup}
```

Here, we do not have a circuit equation (i.e., logical statements involving multiple rather independent circuits), but a circuit progression. Since only in one circuit we have a description of the registers, we declare them without an initial text and put their initialization into `init` gates. The mapping in between is done by using the optional argument of the `\equals` macro. In order to obtain the braces at the ends, we use empty `output` and `init` gates.

## 1. Perfecting Vertical Alignment




$$|0\rangle \begin{array}{c} \oplus \\ \bullet \\ \oplus \end{array} = |0\rangle \begin{array}{c} \bullet \\ \oplus \end{array}$$

Updated in 0.5, 0.4

```
% \useyquantlanguage{groups}
\begin{yquantgroup}
  \registers{
    qubit {} q;
    qubit {\ket{0}} q[+1];
  }
  \circuit{
    cnot q[0] | q[1];
    cnot q[1] | q[0];
    cnot q[0] | q[1];
  }
  \equals
  \circuit{
    cnot q[1] | q[0];
    cnot q[0] | q[1];
  }
\end{yquantgroup}
```

## D. Scaling




```
\begin{tikzpicture}[scale=1.5]
  \begin{yquant*}
    h a;
    phase {\beta} a;
    h a;
  \end{yquant*}
\end{tikzpicture}
```

Here, we first scaled the circuit itself. The default style for `/yquant/every circuit` sets the `transform shape` key for every node (which means any gate), so that those are also scaled. If your `TikZ` version is at least 3.1.6a, this is all that needs to be done. In earlier versions, there was a bug that required `yquant` to reset the `transform shape` key for labels, which would then require you to scale those manually.




### 6.3.6 VII. Typesetting

#### A. Global Styling




```
% \usetikzlibrary{quotes}
\begin{tikzpicture}
  \begin{yquant*}[operators/every h/.append style={fill=red!20}]
    h a;
    phase {\beta} a;
    h a;
    ["\ket{\pm}" above right]
    measure a;
  \end{yquant*}
\end{tikzpicture}
```

Instead of setting `/yquant/operators/every h`, we could also have changed `/yquant/operators/every box`. Had we used `/yquant/every operator`, then the measurement would also have changed. Again, due to a **TikZ** limitation, it is not possible to change the position of labels on a per-style basis, only by using `label` options or a global setting.



```
\begin{tikzpicture}[thick]
  \begin{yquant*}[every operator/.prefix style={fill=white}]
    cnot a[1] | a[0];
    box {\R_z(-\theta\fracslash2)} a[1];
    cnot a[1] | a[0];
    box {\R_z(\theta\fracslash2)} a[1];
    measure a[1];
  \end{yquant*}
\end{tikzpicture}
```

As the “thin” style is the default, we present the opposite. By default, all operators are transparent; we changed this by giving all of them a white background color (but as a style *prefix*, so that, e.g., black fillings overwrite this). Contrary to **quantikz**, this also fills the **cnots**. If you only want to fill certain operators, you have to selectively target them using their styles.




Updated in 0.1.2,  
0.1.1

```
\begin{tikzpicture}
  \begin{yquant}[operators/every box/.append style={fill=white}]
    qubit {} j[3];
    box {$J_{12}$} (-j[1]);
    box {$J_{13}$} (j[0, 2]);
    box {$J_{23}$} (j[1]-);
  \end{yquant}
\end{tikzpicture}
```


`yquant` properly splits discontinuous multi-qubit operations.

## B. Per-Gate Styling



```
% \usetikzlibrary{quotes}
\begin{tikzpicture}
  \begin{yquant*}
    [fill=red!20, font=\color{cyan}]
    h a;
    [green]
    phase {[green]$\beta$} a;
    ["$\ket{\pm}$", blue]
    measure a;
    discard a;
  \end{yquant*}
\end{tikzpicture}
```

Updated in 0.4



Updated in 0.4

```


% \usetikzlibrary{shapes.symbols, fit}
\begin{tikzpicture}
  \begin{yquant}
    qubit {} data;
    qubit {\ket{0}} anc1[2];

    h data;
    cnot anc1 | data;
    [after=data]
    qubit {\ket{0}} anc2[2];
    [name=box, draw=none]
    box {\phantom{noise}} (data, anc1);
    cnot anc2[0] | data;
    cnot anc2 | anc1[0];
    cnot anc2[1] | anc1[1];
    measure anc2[0];
    [blue] measure anc2[1];
  \end{yquant}
  \node[starburst, cyan, fill=yellow, draw=red, line width=2pt,
    inner xsep=-4pt, inner ysep=-5pt, fit=(box)] {noise};
\end{tikzpicture}

```

**TikZ** shapes cannot simply be used with **yquant**. Any **yquant** shape must be aware of the keys `x radius` and `y radius` that control its width and height. Additionally, **yquant** shapes must implement clipping paths. Those objects, which are a **yquant** addition to **TikZ** allow **yquant** to properly clip wires and vertical lines to the shape of the gate. **yquant** draws its elements sequentially; hence, a wire that comes into an operator will be hidden by anything the operator draws on top of it; but outgoing wires will in turn draw on the operator (modulo clipping). To avoid the issues, we construct an invisible box operator and name it; *outside* of the **yquant** environment, we fit the special **TikZ** shape on top of it.

### C. Boxing/Highlighting Parts of a Circuit




Updated in 0.2

```

% \usetikzlibrary{quotes, fit}
\begin{tikzpicture}
  \begin{yquant*}
    h a;
    cnot b | a;
    [name=left]
    h -;
    cnot b | a;
    [name=right]
    h -;
    cnot b|a;
    h b;
  \end{yquant*}
  \node[fit=(left-0) (left-1) (right-0) (right-1),
    draw, inner sep=6pt, "reversed c-\textsc{not}"] {};
\end{tikzpicture}

```

As usual, subcircuits provide a similar experience, but respect the separation:




```

% \usetikzlibrary{quotes}
\begin{tikzpicture}
  \begin{yquant*}
    h a;
    cnot b | a;
    [this subcircuit box style={inner ysep=6pt, "reversed
    ↪ c-\textsc{not}"}]
    subcircuit {
      qubit {} x;
      qubit {} y;
      h -;
      cnot y | x;
      h -;
    } (-);
    cnot b | a;
    h b;
  \end{yquant*}
\end{tikzpicture}

```

Here, we used the key `/yquant/this subcircuit box style` to influence only the style of the subcircuit box itself instead of providing global options

that apply to every object in the subcircuit (you wouldn't want the label be assigned to every single gate).



Updated in 0.4

```
% \usetikzlibrary{quotes}
\begin{tikzpicture}
\begin{yquant*}
  h a;
  [this subcircuit box style={draw, dashed, rounded corners,
    ↪ fill=blue!20, inner ysep=10pt, "\textsc{swap}" below},
    ↪ register/default name=]
  subcircuit {
    qubit a;
    qubit b;
    cnot b | a;
    cnot a | b;
    cnot b | a;
  } (a-b);
  h b;
\end{yquant*}
\end{tikzpicture}
```


Since version 0.2, fully enclosing a bunch of operations (with no controls extending to some inner component) is possible by means of `subcircuits`. Before, this had to be done using named operations and layers. Note that here we used the style `/yquant/this subcircuit box style` to assign a styling that only applies to the box containing the subcircuit, but not to the inner gates—which would have happened had we just given the arguments to the subcircuit directly.

`yquant` does not support the fancy nearest-neighbor swap gate that `quantikz` has. It would however not be very difficult to implement this particular shape and make it available. Maybe even a multi-swap gate using the `knots` library would be possible.

### 6.3.7 VIII. Otherwise undocumented features



Updated in 0.4




```
% \usetikzlibrary{quantikz,fit}
\begin{tikzpicture}
  \begin{yquant}[register/default name=]
    qubit a;
    [name=wave, register/minimum height=5mm, register/minimum depth=5mm]
    nobit wave;
    qubit b;
    qubit c;

    h a, b;
    box {$U$} c | a;
    [draw=none]
    box {$\dots$} a, b-;
    box {$U^k$} c | b;
    h a, b;
  \end{yquant}
  \node[wave, fit=(wave) (current bounding box.east |- wave), inner
    \hookrightarrow ysep=.5pt, inner xsep=0pt] {};
\end{tikzpicture}
```

Here, we included `quantikz`, which provides the wave shape, then introduced a register that will contain this wave (and enlarged it sufficiently). After the circuit is drawn, we fit the wave along. Since the name assigned to a register without any text actually is of a coordinate shape, we need to enlarge the height of the wave by providing a slightly increased `inner ysep`. Additionally, `quantikz` sets a negative `inner xsep`, which is probably required for its grid layout; but `yquant` positions exactly, so we also need to reset this.

`yquant` does not provide a shape corresponding to the “creating an ebit” gate.

### 6.3.8 X. Troubleshooting



Updated in 0.4

```
\begin{tikzpicture}
\begin{yquant}
qubit {\ket{0}} a[2];
box {\begin{pmatrix}
\alpha & \beta \\
\beta & -\alpha
\end{pmatrix}} a[0];
cnot a[1] | a[0];
box {U_{\The\numexpr\idx+1}} a;
\end{yquant}
\end{tikzpicture}
```

## 7 Foreign language support and extensions

`yquant` is built in various modules, so that it is not hard to use the quantum circuit rendering backend, but expose a different language frontend. `yquant` not only understands its own language, but also others. Although we refer to “foreign languages,” additional extension packages of the `yquant` language itself are also covered in this section and can be loaded by the same syntax.

New in 0.3

New in 0.5

### 7.1 groups

New in 0.5

By saying `\useyquantlanguage{groups}` in the preamble after loading `yquant` itself, additional support for groups of `yquant` circuits is loaded. Various circuits in a group share a common set of registers, are appropriately aligned horizontally if on the same line and can also be aligned vertically among multiple lines. The main intended use is for circuit equations.

This extension provides the environment `yquantgroup`. You may use this environment within a `tikzpicture`; in this case, all page-break related features are not available. You may alternatively use the environment outside of a `tikzpicture`; in this case, it will start and end the pictures appropriately.

As with `yquant`, the environment accepts optional options that are passed to `\yquantset`; a starred form is available that allows for the lazy creation of registers—but note that *shared* registers must always be created explicitly; only if some circuits in the group have additional registers, the lazy creation applies.

#### 7.1.1 General usage

```
% preamble:
% \usepackage[compat=<version>]{yquant}
% \useyquantlanguage{groups}
\begin{tikzpicture}% tikz options possible. This environment may be omitted.
  % tikz commands go here
  \begin{yquantgroup}% yquant(group) options possible.
    \registers{
      % arbitrary shared register declaration go here
    }
    % any of \circuit, \equals, \, \shiftright
    % if the tikzpicture environment was omitted: also allows
    % \pagebreak, \newpage, \clearpage, \cleardoublepage
    % in most cases, TikZ commands are also allowed
  \end{yquantgroup}
  % tikz commands go here
\end{tikzpicture}
```



### 7.1.2 Special macros

**\registers** The **\registers** macro can and must only be used once in a **yquantgroup** environment. It contains the declaration of all the registers that are shared among the various circuits within a group. Basically, if you follow the convention in a usual **yquant** circuit to first declare all the registers, then use the gates, then you would put the declaration part in the **\registers** macro. However, note that it is in principle also possible to mix register declarations with other gates and **TikZ** commands.

In case you do not use the **import** gate in any of the circuits within the group and you do not declare own registers, the behavior is very straightforward: basically, the content of **\registers** is copied verbatim at the beginning of each circuit. Otherwise, the general rule is: importing a register will ensure that all non-declaration commands that preceded this register declaration are executed; and importing the last register will additionally execute all succeeding commands within **\registers**.

**\circuit[<style>]{<content>}** The **\circuit** macro can be thought of as starting a **yquant** (or **yquant\***) environment and using its mandatory argument **<content>** as the content of the circuit; the optional **<style>** is used to apply additional styling options to the circuit.

This is not entirely accurate: In reality, the content is put into a **subcircuit** and **<style>** is passed as arguments to the **subcircuit**.

The default style **/yquant/operators/every group circuit** is applied to the circuit. This style is configured such that the illusion of working in a top-level **yquant** environment is very convincing: The circuit is frameless by default and uses the transparent name mangling scheme.

All the registers that were previously defined via **\registers** are automatically available within the circuit, as if their declaration had been copied. In fact, **yquant** will make a register available the first time it is referenced in some gate; if at the end of a circuit some of the shared registers were not used, they will be imported before exiting the circuit. Consequently, if you define own registers just for a single circuit, these will always be at the very top. This can be influenced by means of the **import** gate, which is only available in group **\circuits**. This gate allows to import a declared register at an arbitrary position.

**\equals\*<content>** The **\equals** macro inserts a blank text—internally, a **box**-like gate with the style **/yquant/operators/every group equals**—that contains **<content>**. If omitted, **<content>** is given by **\$=\$**.

The optional star will put a horizontal alignment mark at the position where the box is inserted. Similar to the `&` operation in `amsmath`'s `align` environment or the `\>` in `TEX`'s native `tabbing`, `yquant` will now remember the horizontal position of the box internally and will allow you to directly jump to this position in the next line. Note that you may well have multiple alignment marks in a single line, which `yquant` internally numbers 1, 2, ....

`\\[<separation>]` The `\\` macro inserts a line break (never a page break), so that the next `\circuit` or `\equals` will be put below all circuits that were output before, and it will again start at the same left position as the first circuit. The default vertical distance is given by `/yquant/group/line separation`, but it may be overwritten by the optional `<separation>` argument, which must be a `TEX` dimension.

Note that if you *set* new alignment marks in a new line, this will delete the alignment marks that were previously set.

If the option `/yquant/group/aligned` is passed to the `yquantgroup` environment, the command `\shiftright` is implied after each linebreak.

`\shiftright*[<where>]` The `\shiftright` command will put the “cursor,” i.e., the horizontal position at which the next `\circuit` or `\equals` will start, at the position specified by `<where>`. By default, `<where>` is 1. If the optional star is present, `yquant` will additionally put an alignment mark at this position (see the documentation for `\equals`). If the option `/yquant/group/aligned` is passed to the `yquantgroup` environment, the command `\shiftright` is implied after each linebreak or starred page break.

The option `<where>` can take various forms:

- It may be a natural number 1, 2, ..., denoting the number of an alignment mark specified in a previous line.
- It may be the number 0, denoting the very beginning of the line; this is useful if the `/yquant/group/aligned` option is given, but for a specific line, no alignment should be performed.
- It may be a `TEX` dimension, in which case this dimension is directly added to the cursor (so it is a relative value). This is where passing the optional star makes most sense. If you want to position absolutely, you may first issue `\shiftright[0]` followed by a shift by the dimension that you want.



The macro is named `\shiftright`; however, `yquant` does not enforce that the actual position is to the right of the current position. You may indeed be able to create overlapping circuits if you shift back to a previous position.

`\pagebreak*`, `\newpage*`, `\clearpage*`, `\cleardoublepage*` The page breaking commands are available only if the `yquantgroup` was not enclosed in a `tikzpicture`. They will end the current picture environment, issue the original page breaking command, and start a new picture. Hence, if you want to pass options globally to the picture, you should use the `/yquant/preamble` option for the `yquantgroup`; the content of this key will be passed as options for every implicitly started `tikzpicture`.

Usually, remembering the horizontal alignment marks on a new page does not make much sense. For this reason, the commands will delete all alignment; use their starred versions to retain them. If the option `/yquant/group/aligned` is passed to the `yquantgroup` environment, the command `\shiftright` is implied after the starred version of the page break.

Typically, you will not want to refer to named gates in a circuit on a different page; remember that if you need this feature, you must pass the `remember picture` key in the `/yquant/preamble` option, as this is a reference to another `tikzpicture`. Also don't forget to use the `(TikZ)` overlay key on the corresponding path that references the node in order not to mess up with the bounding box (see the `TikZ` documentation for those two keys).

### 7.1.3 Configuration

Loading the `groups` language extension will define several new configuration keys.

`/yquant/group/every group` default: `default:`  
Style that is installed for every `yquantgroup` and `yquantgroup*` environment, as if it had been given as an option. The style's default path is `/tikz`.

`/yquant/group/line separation` default: `5mm`  
This is the default vertical line separation that is inserted whenever a new line is issued in a `yquantgroup`.

`/yquant/group/aligned` default: `false`  
This boolean flag defines whether `\shiftright` is automatically issued after `\\` and the starred page breaking commands.

`/yquant/preamble` default:

This style may only be passed to the `yquantgroup` alignment directly as an option; it is not available via `\yquantset` and the like. It is only relevant if the `yquantgroup` is not contained in a `tikzpicture`. The content of this style will be given as an optional argument to the `tikzpicture`; this is the recommended way to specify `TikZ` options, as they are automatically preserved among page breaks.

`/yquant/operators/every group circuit` default: `/yquant/operators/every subcircuit, /yquant/operators/subcircuit/frameless, /yquant/operators/subcircuit/name mangling=transparent`

This style is installed for the `subcircuit` that implicitly wraps each `\circuit`. Note that some magic is carried out to ensure that the name mangling setting only applies to the *direct* content of the `\circuit`; any `subcircuits` within the `\circuit` will use the default name mangling scheme.

`/yquant/operators/every group equals` default: `shape=yquant-rectangle, align=center, inner xsep=1mm, x radius=2mm, y radius=2.47mm`

This style is installed for every `\equals`, which is internally realized similarly to a `box` gate.

#### 7.1.4 Gates and operations

No gates or operations may be used directly within the `yquantgroup` environment, but all the usual `yquant` gates and operations are available within `\registers` and `\circuit`. Additionally, within `\circuit`, the `import` gate is available.

`import`

Syntax: `import <target>;`

This is a pseudo-gate that makes all the outer registers given in `<target>` available in the current circuit. Consequently, the register names that are specified in `<target>`, also ranges, do not refer to the registers in the *current* `\circuit`, but instead to those defined via `\registers`. Therefore, it is for example possible to import all outer registers at once using `import -;`. Vector registers can also be imported partially.

If additional content (TeX commands such as `TikZ` paths, non-creation gates) is used within `\registers`, everything that comes *before* the declaration of a register will be copied into the `\circuit` when the register is imported; for a vector, this refers to the index zero. Additionally, any additional content that comes *after* the declaration of the last register will be copied directly after the last register was imported.



### Out-of-order importing

Note that it is principle possible to import registers out-of-order. Since matching outer and inner wires in subcircuits is done in the order in which they appear, this will lead to inner registers with names that do not match their outer registers and is probably highly undesirable.

Usually, this gate will not be needed as `yquant` will automatically import an outer register upon its first use.

*Possible attributes:* none

## 7.2 qasm

By saying `\useyquantlanguage{qasm}` in the preamble after loading `yquant` itself, the parser for `qasm` (not OpenQASM) is loaded. It provides the environment `qasm` as well as the macro `\qasmimport`, which works similarly to `\yquantimport` (but does not accept additional options).

### 7.2.1 Language specification

The `qasm` language is not formally defined, but an overview is provided at [the archived website of qasm2circ](#). The `yquant` implementation is designed to be compatible with the original parser, with the following exceptions:

- In `qasm`, lines could begin in an arbitrary manner; the first whitespace followed by the first valid command were then the instruction. Contrary to this, `yquant`'s parser always expects a line to start with a valid gate (preceded by arbitrary whitespaces), a comment, or to be empty.
- In `qasm`, user-defined gates will be drawn in a box unless they contain the text `\dmeter`, and they will be recognized as measurement gates if they contain `\meter` or `\dmeter`. Contrary to this, `yquant`'s parser expect the gates to *start* with one of the macros `\meter`, `\dmeter`, or `\dmeterwide`. Using these macros *within* the content of a gate does not make sense from the point of view that in `yquant`, gates are nodes with shapes, so either the full gate has a particular shape or it does not, but not only parts of it.
- The space gate is supposed to produce a horizontal whitespace without a gate. In `yquant`'s implementation, you have to discard the wire if you want to reproduce this behavior; space and nop are equivalent.

The default `qasm` style defines several macros that can be used in gates. `yquant` makes `\m` (matrix; requires `amsmath`) and `\txt` (switch to text mode) available within the `qasm` environment.

Do not expect `yquant`'s output to match the one of `qasm` exactly. `yquant` is not grid based, so that commands such as `nop` don't even make sense. They are implemented for compatibility reasons and will produce a fixed horizontal space of the operator minimum width plus one separation, which might or might not be accurate.

Note that whatever you write between `\begin{qasm}` and `\end{qasm}` is essentially treated as verbatim; only where the specification says so (in the definition of a new gate and in the optional third command to the register definition), it is interpreted as TeX markup. Consequently, in `beamer`, any frame containing these environments must be given the `fragile` option.

### 7.2.2 Configuration

Loading the `qasm` language interpreter will define several new configuration keys. For all the gates, it will use the keys defined in section 3, and it additionally provides the following:

`/yquant/operators/every s`                      default: `/yquant/operators/every box`  
This style is installed for every `s` operator.

`/yquant/operators/every t`                      default: `/yquant/operators/every box`  
This style is installed for every `t` operator.

`/yquant/operators/every utwo`                      default: `/yquant/operators/every box`  
This style is installed for every `Utwo` operator.

`/qasm/zero`    default: `\qasm@ket0`  
The content of this macro is used as the initialization content whenever the zero gate is invoked.

`/qasm/register/default qubit name`                      default: `\qasm@ket{#1}`  
This macro is invoked with a single parameter (the name of a qubit register) and gives back what is printed as the name of the register (will be in math mode automatically).

/qasm/register/default qubit name value      default:  $\backslash\text{qasm@ket}\{ \#1 \} =$   
 $\backslash\text{qasm@ket}\{ \#2 \}$


This macro is invoked with two parameters (the name of a qubit register and its initial value) and gives back what is printed as the name of the register (will be in math mode automatically).

### 7.2.3 Examples


The unaltered .qasm files provided from [the qasm2circ page](#) were stored in the subfolder qasm relative to this manual's T<sub>E</sub>X file. The following command is then used to print all of them:

```
% preamble:
% \usepackage[compat=<version>]{yquant}
% \usepackage{import}
% \useyquantlanguage{qasm}
\def\yquantimportpath{qasm/}
\foreach \circuitno in {1, ..., 18} {
  \paragraph{Circuit \#\circuitno}
  \begin{center}
    \qasmimport{test\circuitno.qasm}
  \end{center}
}
```


Circuit #1




Circuit #2




Circuit #3




**Circuit #4**




**Circuit #5**




**Circuit #6**



**Circuit #7**




**Circuit #8**







**Circuit #9**




**Circuit #10**




**Circuit #11**




**Circuit #12**




**Circuit #13**







**Circuit #15**




**Circuit #16**



**Circuit #17**



**Circuit #18**



## 8 Wishlist

This section contains some thoughts on future improvements and features.

- Support for more other languages.  
Since version 0.3, `yquant` understands `qasm`. It would be nice if `yquant` could also understand OpenQASM correctly. The way OpenQASM treats operations is a bit different from `yquant` and also `qasm`. Some machinery would be required to automatically carry out transversal gates; apart from that everything should be available in `yquant`.
- Vertical layout.  
Sometimes, long quantum circuits on a portrait page can be better represented in a vertical layout. Also if lots of explanations are to be added, this becomes problematic in the horizontal version. In principle, `yquant`'s approach could allow for a simple key switch that changes horizontal to vertical. Currently, this is largely unsupported by all quantum circuit packages except for `qpqc`.

## 9 Changelog

### 2020-03-15: Version 0.1

Initial release

### 2020-03-22: Version 0.1.1

Complete rewrite of the register name parser. `yquant` now understands comma-separated lists and ranges in indices, and also is far more tolerant with respect to whitespaces.

`yquant` now also supports non-contiguous vector registers and allows to add new registers into an already existing vector that is not the last register, and also in the unstarred mode.

### 2020-04-11: Version 0.1.2

Introduce `setstyle` and `addstyle` pseudo-gates that allow to style individual wires; rename `setwire` to `settype` (the old name is still available and shows a deprecation warning).

Complete rewrite of the way `yquant` draws wires; projection anchors are removed in favor of clipping paths. This allows perfect connections between gates and wires, even if the (rather rectangular) wire lines meets with nonplanar shapes, while still preserving the possibility of transparent wires.

`yquant` now also properly draws non-contiguous multi-qubit operations.

New gate: `correlate`. Various bug fixes.

### 2020-06-02: Version 0.2

Introduce `subcircuit`; required rewriting how `yquant` internally positions vertically. Provide simple macros to load circuits (or parts) from a file and to declare own custom gates.

### 2020-06-07: Version 0.2.1

Introduce a macro to declare a lightweight custom gate, which is only a single box with custom content.

### 2020-06-13: Version 0.3

Introduce support for the `qasm` language.

### 2020-07-11: Version 0.3.1

Add legacy support for very old `TikZ` versions such as the one used on the arXiv.

### 2020-08-24: Version 0.3.2

Fix #5: Can't draw circuits with more than 9 qubits.

### 2020-10-27: Version 0.3.3

Fix #6: shorten doesn't work for 2-qubit barriers. This fixes a bug in how the shorten keyword worked on `barriers`, which may require re-assessing your chosen values.

### 2021-02-21: Version 0.4-alpha

Lots of internal fixes, most notably vertical alignment with subcircuits.

Introduce capability to perform vertical alignment with multi-register gates.

Dramatic changes under the hood regarding horizontal positioning, which is now only determined in the drawing stage; this paves the way for delayed gates, which are planned for 0.4. Also changes in the gate declaration interface.

Introduce compatibility layer, so that layout-breaking changes will not become effective unless explicitly requested.

Separate register height into a height and depth key.

Introduce `overlay` key to disable height calculation selectively.

Change register style declaration, so that this is now always equivalent to creating an unnamed register followed by an `init` gate with the given text. Note: This may be a **breaking change** that cannot be compatibility-protected—if you used  $\text{\TeX}$  conditionals involving `\idx` for creation labels of registers, you will now need to either `\protect` them all or just capitalize their first letter (which corresponds to auto-protected versions for compat at least 0.4).

Now use nodes for `init` and `output` gates.

Change behavior of `hspace` and `align`: Now also extend if the wire is discarded afterwards.

Introduce the commands `\Ifnum`, `\Ifcase`, `\Or`, `\Else`, `\Fi`, `\Unless` and `\The` available for use within gates that behave like auto-`\protected` versions of their plain  $\text{\TeX}$  equivalents.

### 2021-03-27: Version 0.4

New gate: `inspect`. Various bug fixes.

Introduce the `direct control` feature: `measure` gates can now substitute positive controls of future gates.

### 2021-07-03: Version 0.4.1

Fix #9: Output bracket misaligned.

Fix #10: Unable to access node in subcircuit. As of this version, named nodes in subcircuits will also be properly aliased if there is only a single target subcircuit (so that you don't need to use the `-0` suffix for the subcircuit's name).

### 2021-08-17: Version 0.5

Improvement: Active outer canvas transformations (`TikZ` shifts, scalings, rotations) should be supported more nicely (no guarantees!).

Improvement: Custom gates (`\yquantdefinegate`) can now contain `TikZ \path-` like commands without the `\noexpand` prefix.

Improvement: Automatically discard wires *inside* a subcircuit (even if they had the `out` or `inout` attribute) if they are discarded directly after the subcircuit *and* they have output gates within the subcircuit (else, the wire would be re-drawn from the output to the border of the subcircuit).

Bugfix: Referencing named gates in nested subcircuits now works without producing an error (worked before, but gave errors).

Bugfix: Properly handle the `direct control` feature if it was specified, but not used until the end of the (sub)circuit.

Introduce name mangling options for subcircuits.

Implement #11: Circuit equations. As of this version, the `groups` language is available that allows to easily implement circuit equations.